

SUMMARY OF QUANTITIES			URBAN		
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				IL. RTE. 58 BRIDGE SFTY-2A	IL. RTE. 72 BRIDGE SFTY-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.4	0.1	0.3
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	74	27	47
44000100	PAVEMENT REMOVAL	SQ YD	2,365	1,048	1,317
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	873	321	552
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2,946	1,446	1,500
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	18,706	9,254	9,452
50101700	REMOVAL OF EXISTING SUPERSTRUCTURES NO. 1	EACH	1	1	
50101800	REMOVAL OF EXISTING SUPERSTRUCTURES NO. 2	EACH	1		1
50300100	FLOOR DRAINS	EACH	22	18	4
50300255	CONCRETE SUPERSTRUCTURES	CU YD	90.8	56.6	34.2
50300260	BRIDGE DECK GROOVING	SQ YD	724	466	258
50300300	PROTECTIVE COAT	SQ YD	1,152	766	386
50400205	PRECAST PRESTRESSED CONCRETE DECK BEAMS (11" DEPTH)	SQ FT	3,236		3,236
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	6,300	6,300	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3,500	1,500	2,000
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	24,480	17,540	6,940
50800515	BAR SPLICERS	EACH	115	71	44
51500100	NAME PLATES	EACH	2	1	1
50901720	BICYCLE RAILING	FOOT	70	70	
50901750	PARAPET RAILING	FOOT	70	70	
60255500	MANHOLES TO BE ADJUSTED	EACH	4	3	1
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	18,706	9,254	9,452
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	37.5	37.5	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	1	2
* 63100105	TRAFFIC BARRIER TERMINAL, TYPE 10	EACH	1	1	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1		1
63200310	GUARDRAIL REMOVAL	FOOT	180	78	102
63300575	REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARD RAIL	FOOT	58	58	

SUMMARY OF QUANTITIES			URBAN 100% STATE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				IL. RTE. 58 BRIDGE SFTY-2A	IL. RTE. 72 BRIDGE SFTY-2A
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	30	30
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,395	2,054	2,341
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,387.5	1,275	1,112.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2,387.5	1,275	1,112.5
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,675	1,263	2,412
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,083	907	176
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8	4	4
* 78100300	REPLACEMENT REFLECTOR	EACH	100	50	50
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,800	790	1,010
X0321743	SILICONE JOINT SEALER, 1"	FOOT	102	102	
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	120.8	69.4	51.4
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	176	102	74
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	14	5	9
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	164	25	139
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	13,186	6,162	7,024
X0712400	TEMPORARY PAVEMENT	SQ YD	2,365	1,048	1,317
X5030304	CONCRETE WEARING SURFACE, 4"	SQ YD	572	572	
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	292		292
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	46	46	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	2	2
Z0030340	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	2	2
Z0073700	TEMPORARY WALL BRACING SYSTEM	L SUM	1		1

\* SPECIALTY ITEM

FILE NAME = 60055 summary.dgn  
PLOT DATE = 6/25/2008



DESIGNED - S.J.P.  
DRAWN - A.C.S.  
CHECKED - E.J.M.  
DATE - APRIL 21, 2008

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

Rev. 7-15-08  
SUMMARY OF QUANTITIES  
IL. RTE. 58 & IL. RTE. 72

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE. 58/72 SECTION 2008-007 B COUNTY COOK TOTAL SHEETS 39 SHEET NO. 3 CONTRACT NO. 60D55  
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT