

| SUMMARY OF QUANTITIES | | | LABAN | | |
|-----------------------|--------------------------------------------------------------|-------|-----------------------------------|----------------------------------|----------------------------------|
| CODE NO | ITEM | UNIT | 100% STATE TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | |
| | | | | IL. RTE. 58 BRIDGE SFTY-2A | IL. RTE. 72 BRIDGE SFTY-2A |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 0.4 | 0.1 | 0.3 |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 74 | 27 | 47 |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 2,365 | 1,048 | 1,317 |
| 44000155 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | SQ YD | 873 | 321 | 552 |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 2,946 | 1,446 | 1,500 |
| 44002020 | CONCRETE MEDIAN SURFACE REMOVAL | SQ FT | 18,706 | 9,254 | 9,452 |
| 50101500 | REMOVAL OF EXISTING SUPERSTRUCTURES | EACH | 2 | 1 | 1 |
| 50300100 | FLOOR DRAINS | EACH | 22 | 18 | 4 |
| 50300255 | CONCRETE SUPERSTRUCTURES | CU YD | 90.8 | 56.6 | 34.2 |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 724 | 466 | 258 |
| 50300300 | PROTECTIVE COAT | SQ YD | 1,152 | 766 | 386 |
| 50400205 | PRECAST PRESTRESSED CONCRETE DECK BEAMS (11" DEPTH) | SQ FT | 3,236 | | 3,236 |
| 50400605 | PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH) | SQ FT | 6,300 | 6,300 | |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 3,500 | 1,500 | 2,000 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 24,480 | 17,540 | 6,940 |
| 50800515 | BAR SPLICERS | EACH | 115 | 71 | 44 |
| 51500100 | NAME PLATES | EACH | 2 | 1 | 1 |
| 50901720 | BICYCLE RAILING | FOOT | 70 | 70 | |
| 50901750 | PARAPET RAILING | FOOT | 70 | 70 | |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 4 | 3 | 1 |
| 60618300 | CONCRETE MEDIAN SURFACE, 4 INCH | SQ FT | 18,706 | 9,254 | 9,452 |
| * 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 37.5 | 37.5 | |
| * 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 3 | 1 | 2 |
| * 63100105 | TRAFFIC BARRIER TERMINAL, TYPE 10 | EACH | 1 | 1 | |
| * 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 1 | | 1 |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 180 | 78 | 102 |
| 63300575 | REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARD RAIL | FOOT | 58 | 58 | |

| SUMMARY OF QUANTITIES | | | LABAN | | |
|-----------------------|----------------------------------------------------------------------|--------|-----------------------------------|----------------------------------|----------------------------------|
| CODE NO | ITEM | UNIT | 100% STATE TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | |
| | | | | IL. RTE. 58 BRIDGE SFTY-2A | IL. RTE. 72 BRIDGE SFTY-2A |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 3 | 3 |
| 67100100 | MOBILIZATION | L SUM | 1 | 0.5 | 0.5 |
| 70101800 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 0.5 | 0.5 |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 60 | 30 | 30 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 4,395 | 2,054 | 2,341 |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 2,387.5 | 1,275 | 1,112.5 |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 2,387.5 | 1,275 | 1,112.5 |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 3,675 | 1,263 | 2,412 |
| * 78008210 | POLYUREA PAVEMENT MARKING TYPE I - LINE 4" | FOOT | 1,083 | 907 | 176 |
| * 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 8 | 4 | 4 |
| * 78100300 | REPLACEMENT REFLECTOR | EACH | 100 | 50 | 50 |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 1,800 | 790 | 1,010 |
| X0321743 | SILICONE JOINT SEALER, 1" | FOOT | 102 | 102 | |
| X0322467 | TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE | SQ FT | 120.8 | 69.4 | 51.4 |
| X0323076 | SILICONE JOINT SEALER, 1 3/4" | FOOT | 176 | 102 | 74 |
| X0325303 | STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES) | SQ FT | 14 | 5 | 9 |
| X0325305 | STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES) | SQ FT | 164 | 25 | 139 |
| X0325775 | WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH | FOOT | 13,186 | 6,162 | 7,024 |
| X0712400 | TEMPORARY PAVEMENT | SQ YD | 2,365 | 1,048 | 1,317 |
| X5030304 | CONCRETE WEARING SURFACE, 4" | SQ YD | 572 | 572 | |
| X5030305 | CONCRETE WEARING SURFACE, 5" | SQ YD | 292 | | 292 |
| Z0001900 | ASBESTOS BEARING PAD REMOVAL | EACH | 46 | 46 | |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 0.5 | 0.5 |
| Z0030240 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2 | EACH | 4 | 2 | 2 |
| Z0030340 | IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2 | EACH | 4 | 2 | 2 |
| Z0073700 | TEMPORARY WALL BRACING SYSTEM | L SUM | 1 | | 1 |

* SPECIALTY ITEM

FILE NAME = 60D55 summary.dgn
PLOT DATE = 6/25/2008

CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

| | | | |
|------------|----------------|-----------|--|
| DESIGNED - | S.J.P. | REVISED - | |
| DRAWN - | A.C.S. | REVISED - | |
| CHECKED - | E.J.M. | REVISED - | |
| DATE - | APRIL 21, 2008 | REVISED - | |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
IL. RTE. 58 & IL. RTE. 72**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

| | | | | |
|---------------------------------------------------|--------------------|-------------|--------------------|-------------|
| F.A.P. RTE. 58/541 | SECTION 2008-007 B | COUNTY COOK | TOTAL SHEETS 39 | SHEET NO. 3 |
| FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT | | | CONTRACT NO. 60D55 | |

Rev.