

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY 100% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000	BRIDGE X081-2A
20200100	EARTH EXCAVATION	CU YD	71	71	
25000210	SEEDING, CLASS 2A	ACRE	0.02	0.02	
25100630	EROSION CONTROL BLANKET	SQ YD	100	100	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	227		227
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	46	46	
44000100	PAVEMENT REMOVAL	SQ YD	111	111	
44000700	APPROACH SLAB REMOVAL	SQ YD	107		107
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	100	100	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	4.5		4.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	6.4		6.4
50300260	BRIDGE DECK GROOVING	SQ YD	353		353
50300300	PROTECTIVE COAT	SQ YD	383		383
X50230305	CONCRETE WEARING SURFACE, 5"	SQ YD	383		383
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	3443		3443
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5850		5850
50800515	BAR SPLICERS	EACH	116		116
50901050	STEEL BRIDGE RAIL, TYPE SM	FOOT	204		204
51500100	NAME PLATES	EACH	1		1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	68		68
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	212.5	212.5	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	408	408	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	1	8
67100100	MOBILIZATION	L SUM	1	0.2	0.8
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	0.2	0.8
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	977	977	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	365	365	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	365	365	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY 100% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000	BRIDGE X081-2A
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3700	3700	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	97	97	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20	20	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4	
* 78200450	MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	10	10	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	36	36	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300105	PAVEMENT MARKING REMOVAL	FOOT	2457	2457	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	48	48	
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1	
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	6	6	
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	6	6	
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	6	6	
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26	
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	6	
X0325239	TEMPORARY PAVEMENT 10"	SQ YD	100	100	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	71		71
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	1456	1456	
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	48	48	
X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	3	3	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	24		24
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.2	0.8
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
* X0326135	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	1	1	
* X0326134	AERIAL CABLE, 3-1/C NO. 2, ALUMINUM, WITH MESSENGER WIRE	FOOT	100	100	
* X8180050	AERIAL CABLE, 3-1/C NO. 40 ALUMINUM, WITH MESSENGER WIRE	FOOT	1300	1300	
* X0326133	TEMPORARY WOOD POLE, 45 FT, CLASS 5	EACH	1	1	

* SPECIALTY ITEM

FILE NAME = MAPROG\3229\3229_21\Design\ProposedPlan\3229_21_rsc.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = jcoleman	DESIGNED - DMM	REVISED -
PLOT SCALE = 1,0000' / IN.	DRAWN - DMM	REVISED -
PLOT DATE = 5/15/2008	CHECKED - MJL	REVISED -
	DATE - 05/13/2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**FAP 631 / ILLINOIS ROUTE 102
ILLINOIS ROUTE 102 OVER FORKED CREEK OVERFLOW
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 631	SECTION 111N-1 B	COUNTY WILL	TOTAL SHEETS 32	SHEET NO. 3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60D85	

Rev.