


- LEGEND:**
- TEMPORARY LIGHTING UNIT
50 FT. MOUNTING HEIGHT, 15 FT. MAST ARM
400 WATT, 120 VOLT LUMINAIRE WITH PHOTOCELL
ON EACH LUMINAIRE
 - AERIAL CABLE, 3-1/C NO. 4, ALUMINUM, WITH MESSENGER WIRE
 - GROUND ROD, 5/8" DIAMETER X 10 FT.
 - ELECTRIC SERVICE DISCONNECT, LIGHTING
AND TRAFFIC SIGNAL
 - EXISTING UTILITY POLE
 - TEMPORARY WOOD POLE, 45 FT, CLASS 5



DATE: 5/13/2008
SEAL EXPIRES: 11/30/2009

- NOTES**
1. TEMPORARY LIGHTING SHALL BE INSTALLED AND OPERATIONAL BEFORE THE START OF CONSTRUCTION.
 2. POLE SHALL BE SETBACK 18 FT. FROM THE EDGE OF THE TRAVELLED PAVEMENT, UNLESS OTHERWISE REQUIRED BY THE FIELD CONDITIONS.
 3. TEMPORARY LIGHTING SHALL REMAIN OPERATIONAL FOR BOTH STAGE I AND STAGE II. STAGE I SHOWN.
 4. ALL POLES SHOWN ON THIS PLAN SHALL BE INSTALLED BY THE LIGHTING CONTRACTOR.

FILE NAME = N:\PROJ\329\329.dwg

Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4008 Fax 773.775.4014

USER NAME = jvondra	DESIGNED - JMV	REVISED -
	DRAWN - MB	REVISED -
PLOT SCALE = 50.0000' / 1" IN.	CHECKED - JMV	REVISED -
PLOT DATE = 5/13/2008	DATE - 05/13/2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**FAP 631/ILLINOIS ROUTE 102
OVER FORKED CREEK OVERFLOW
TEMPORARY LIGHTING PLAN**

SCALE: SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
631	111N-1 B	WILL	32	12
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 60D85	