

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	136 RS-5	LAKE	23	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

D-91-376-08

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN 80% FED. 20% STATE				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	63	63				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14.6	14.6				
40600300	AGGREGATE (PRIME COAT)	TON	73.5	73.5				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5.5	5.5				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	212	212				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	217	217				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1589	1589				
42001300	PROTECTIVE COAT	SO YD	28	28				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	18370	18370				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100				
44002219	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4 3/4"	SO YD	720	720				
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	20	20				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	400	400				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	150	150				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	150	150				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	412	412				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3906	3906				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	291.2	291.2				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN 80% FED. 20% STATE				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14323	14323				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	982	982				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	220	220				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	108	108				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	434	434				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	291.2	291.2				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14323	14323				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	982	982				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	220	220				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	108	108				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	173	173				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	173	173				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	30	30				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	795	795				
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	3	3				

NP=Non-participating
* = Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
ILL 173 (ROSECRANS ROAD)
ILL 131 TO LEWIS AVENUE

5/22/2008 10:00:00 AM