

801.FED.
20/STATE

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	23.1	23.1
40600300	AGGREGATE (PRIME COAT)	TON	115	115
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	177.2	177.2
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	194	194
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	411	411
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3,765	3,765
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	7	7
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	38,415	38,415
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	9	9
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,070	1,070
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	113	113
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	1,836	1,836
42400800	DETECTABLE WARNINGS	SQ FT	12	12
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	400	400
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	32	32
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	190	190
44000600	SIDEWALK REMOVAL	SQ FT	113	113
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	1,597	1,597
44003100	MEDIAN REMOVAL	SQ FT	190	190
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	62	62
60401810	GRATES, TYPE 3	EACH	23	23
60404800	FRAMES AND GRATES, TYPE II	EACH	1	1
60618800	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	190	190
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8000	8000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	436	436
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	23,042	23,042
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,628	1,628
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	480	480
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	259	259
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2640	2640
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	437	437
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	23,042	23,042
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1654	1654
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	480	480
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	259	259
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	501	501
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	501	501
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	664	664
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	77.1	77.1
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75, N50	TON	1615	1615
NP 70018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	48	48
70004500	BITUMINOUS DRIVEWAY PAVEMENT 8"	SQ YD	7	7
70076600	TRAINERS	HOUR	9	9
70004900	BITUMINOUS DRIVEWAY PAVEMENT 10"	SQ YD	9	9

* SPECIALTY ITEM
NP = Non-participating

Rev. 7-16-08

PLOT DATE = 5/22/2008
 FILE NAME = K:\1225588\Civil\Sheets\1225588_SCD.dgn
 USER NAME = jmm
 MODEL = Default



200 West Front Street
Wheaton, IL 60187

DESIGNED - WJV	REVISED -
DRAWN - WJV	REVISED -
CHECKED - BLB	REVISED -
DATE - 5/23/08	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 137 (GREENWOOD AVE. - BLANCHARD RD.)
SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
352	(E, M, D) RS-6	LAKE	21	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60E56	

SCALE: SHEET NO. OF SHEETS STA. TO STA.