

80% FED.
20% STATE

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000-2A
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	23.1	23.1
40600300	AGGREGATE (PRIME COAT)	TON	115	115
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	177.2	177.2
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	194	194
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	411	411
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3,765	3,765
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	38,415	38,415
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,070	1,070
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	1,836	1,836
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	155	155
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	19	19
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	1,597	1,597
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	62	62
60401810	GRATES, TYPE 3	EACH	23	23
60404800	FRAMES AND GRATES, TYPE 11	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,908	4,908
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	436	436
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	23,042	23,042
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,628	1,628
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	480	480
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	259	259
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,636	1,636
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	437	437
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	23,042	23,042
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,628	1,628
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	480	480
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	259	259
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	300	300
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	300	300
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	664	664
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	320.9	320.9
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75, N50	TON	2,020	2,020
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	48	48
Z0076600	TRAINEES	HOUR		

* SPECIALTY ITEM
NP = Non-participating

5/22/2008
5:11:22 PM
K:\11225598\11225598-300.dgn
User: K:\11225598\11225598-300.dgn
Model: Default



200 West Front Street
Wheaton, IL 60187

DESIGNED - WJV
DRAWN - WJV
CHECKED - BLB
DATE - 5/23/08

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 137 (GREENWOOD AVE. - BLANCHARD RD.)
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 352	SECTION (E, M, D) RS-6	COUNTY LAKE	TOTAL SHEETS 21	SHEET NO. 3
CONTRACT NO. 60E56				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				