ROUTE: IL Rte 22 (Rte 43 to Westminster Way)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
200' west of Westminster	Westminster Way	EB	2	3	36	108	12
200' west of Westminster	Westminster Way	EB	2	12	4	48	5
200' west of Westminster	Westminster Way	EB	RT TL	3	48	144	16
200' west of Westminster	Westminster Way	EB	2	2	12	24	3
200' west of Westminster	Westminster Way	EB	2	12	4	48	5
200' west of Westminster	Westminster Way	EB	2	12	4	48	5
200' west of Westminster	Westminster Way	EB	2	12	4	48	5
200' west of Westminster	Westminster Way	EB	2	12	4	48	5
200' west of Westminster	Westminster Way	EB	2	12	4	48	5
Westminster Way	I94 Tollway	EB	1	12	4	48	5
Westminster Way	I94 Tollway	EB	RT TL	3	275	825	92
Westminster Way	I94 Tollway	EB	1	12	4	48	5
Westminster Way	I94 Tollway	EB	1	12	2	24	3
Westminster Way	I94 Tollway	EB	RT TL	12	4	48	5
Westminster Way	I94 Tollway	EB	2	12	4	48	5
I94 Tollway	Lakeside Dr	EB	2	12	4	48	5
I94 Tollway	Lakeside Dr	EB	2	12	4	48	5
I94 Tollway	Lakeside Dr	EB	2	2	100	150	17
Lakeside Dr	Rte 43	EB	2	12	4	48	5
Lakeside Dr	Rte 43	EB	2	2	100	150	17
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	6	24	144	16
Lakeside Dr	Rte 43	EB	1	6	24	144	16
Lakeside Dr	Rte 43	EB	1	6	24	144	16
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	2	3	200	600	67
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	2	4	12	48	5
Lakeside Dr	Rte 43	EB	1	3	30	90	10
Lakeside Dr	Rte 43	EB	2	3	40	120	13
Lakeside Dr	Rte 43	EB	2	12	4	48	5
Lakeside Dr	Rte 43	EB	2	12	4	48	5
Lakeside Dr	Rte 43	EB	2	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Lakeside Dr	Rte 43	EB	2	12	4	48	5
Lakeside Dr	Rte 43	EB	1	12	4	48	5
Rte 43	600' east of	EB	2	12	4	48	5
Rte 43	Rte 43	EB	1	12	4	48	5
Rte 43	600' east of	EB	2	12	4	48	5
Rte 43	Rte 43	EB	2	12	4	48	5
Rte 43	600' east of	EB	2	12	4	48	5

ROUTE: IL Rte 22 (Rte 43 to Westminster Way)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Rte 43	Rte 43	EB	1	12	4	48	5
600' east of Rte 43	Rte 43	WB	2	12	4	48	5
600' east of Rte 43	Rte 43	WB	1	12	4	48	5
600' east of Rte 43	Rte 43	WB	2	12	4	48	5
600' east of Rte 43	Rte 43	WB	2	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	4	12	48	5
Rte 43	Lakeside Dr	WB	1	3	900	2700	300
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	1	12	4	48	5
Rte 43	Lakeside Dr	WB	2	12	4	48	5
Rte 43	Lakeside Dr	WB	2	12	4	48	5
Rte 43	Lakeside Dr	WB	2	3	300	900	100
Lakeside Dr	I94 Tollway	WB	2	12	4	48	5
Lakeside Dr	I94 Tollway	WB	2	12	4	48	5
Lakeside Dr	I94 Tollway	WB	2	12	4	48	5
Lakeside Dr	I94 Tollway	WB	2	3	400	1200	133
I94 Tollway	200' west of Hewitt Dr	WB	1	12	4	48	5
I94 Tollway	200' west of Hewitt Dr	WB	2	12	4	48	5
I94 Tollway	200' west of Hewitt Dr	WB	LT TL	3	100	300	33
I94 Tollway	200' west of Hewitt Dr	WB	1	12	4	48	5
I94 Tollway	200' west of Hewitt Dr	WB	2	12	4	48	5
I94 Tollway	200' west of Hewitt Dr	WB	1	12	8	96	11
I94 Tollway	200' west of Hewitt Dr	WB	2	12	7	84	9
I94 Tollway	200' west of Hewitt Dr	WB	1	12	6	72	8
I94 Tollway	200' west of Hewitt Dr	WB	1	12	2	24	3
I94 Tollway	200' west of Hewitt Dr	WB	1	12	6	72	8
I94 Tollway	200' west of Hewitt Dr	WB	1	12	4	48	5
I94 Tollway	200' west of Hewitt Dr	WB	2	12	4	48	5
I94 Tollway	200' west of Hewitt Dr	WB	2	12	12	144	16
I94 Tollway	200' west of Hewitt Dr	WB	2	12	8	96	11
I94 Tollway	200' west of Hewitt Dr	WB	1	12	6	72	8
I94 Tollway	200' west of Hewitt Dr	WB	1	12	4	48	5
I94 Tollway	200' west of Hewitt Dr	WB	2	12	8	96	11
I94 Tollway	200' west of Hewitt Dr	WB	1	12	6	72	8
I94 Tollway	200' west of Hewitt Dr	WB	2	12	4	48	5
I94 Tollway	200' west of Hewitt Dr	WB	2	12	4	48	5
			TOTALS:		2996		1350 SY

FILE NAME = c:\projects\d136008\design_aa.dgn

USER NAME = wilgreendp | PLOT SCALE = 100.0000 ' / IN. | PLOT DATE = 6/26/2008

DESIGNED - | DRAWN - | CHECKED - | DATE -

REVISED - | REVISED - | REVISED - | REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 22

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-046 RS	LAKE	29	14

CONTRACT NO. 60E95

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

...\projects\d136008\design_aa.dgn 6/26/2008 1:30:57 PM User=wilgreendp