

ACNHF AOBHF ACNHF

ITEM NO.	ITEMS	UNIT	URBAN QUANTITY	TRAFFIC SIGNALS												EMERGENCY VEHICLE PREEMPTION		RIGHT TURN LN (STA. 3167+50 TO STA. 3177+30)	SIDEWALK		
				ROADWAY	CULVERTS	LANDSCAPING	RETAINING WALLS	IL RT 59 @ BLACK ROAD	IL RT 59 @ VERTIN BLVD	IL RT 59 @ STA. 3122+00 LEFT	IL RT 59 @ THEODORE ST	IL RT 59 @ VERMETTE CIRCLE	IL RT 59 @ CATON FARM ROAD	INTERCONNECT	100% SHOREWOOD	100% JOLIET	100% JOLIET	50% STATE 50% SHOREWOOD	50% STATE 50% JOLIET		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2,023	J000-2A	X028-2A	Y003	Y007										Y031-3D	J000-1A	SFTY-1B		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,067	1,067																	
20101000	TEMPORARY FENCE	FOOT	2,976	2,976																	
20101100	TREE TRUNK PROTECTION	EACH	80	80																	
20101200	TREE ROOT PRUNING	EACH	80	80																	
20200100	EARTH EXCAVATION	CU YD	14,915	14,915																	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	17,847	17,847																	
20400800	FURNISHED EXCAVATION	CU YD	91,104	91,104																	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1,184				1,184														
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	14,153	14,153																	
20800150	TRENCH BACKFILL	CU YD	22,098	22,098																	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	4,267	4,267																	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	23,006	23,006																	
21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	41,810	41,810																	
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	7,541	7,541																	
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	2,959	2,959																	
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	200	200																	
25000210	SEEDING, CLASS 2A	ACRE	4.50	4.50																	
25000310	SEEDING, CLASS 4	ACRE	0.75	0.75																	
25000322	SEEDING, CLASS 5A	ACRE	0.75	0.75																	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,134	1,134																	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,134	1,134																	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,134	1,134																	
25000775	SELECTIVE MOWING STAKES	EACH	6	6																	
25003310	INTERSEEDING, CLASS 4	ACRE	0.75	0.75																	
25100115	MULCH, METHOD 2	ACRE	15.25	15.25																	
25100630	EROSION CONTROL BLANKET	SQ YD	28,024	28,024																	
25200110	SODDING, SALT TOLERANT	SQ YD	47,857	47,857																	
25200200	SUPPLEMENTAL WATERING	UNIT	2,441	2,441																	
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	3,229	3,229.0																	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,514	1,514																	
28000500	INLET AND PIPE PROTECTION	EACH	236	236																	
28000510	INLET FILTERS	EACH	410	410																	
28001000	AGGREGATE (EROSION CONTROL)	TON	23	23																	
28100107	STONE RIPRAP, CLASS A4	SQ YD	600		180		420														
28200200	FILTER FABRIC	SQ YD	665		240		425														
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	31,650	31,650																	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	109	108																	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	2,538	2,538																	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,857	1,857																	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,295	1,295																	
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	127,378	126,830																	548
42001300	PROTECTIVE COAT	SQ YD	77,357	77,357																	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	266	266																	

• SPECIALITY ITEM  
 \*\*100% SHOREWOOD QUANTITIES (NOT IDENTIFIED IN FUNDING BREAKDOWNS NOTED ABOVE)

REVISIONS	
NAME	DATE
REVISED IL59 ALIGN.	12/22/06

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 ILLINOIS ROUTE 59  
 DATE 3/18/08  
 DRAWN BY FA  
 CHECKED BY RCB  
 SCALE: NONE

7-18-08

PLAN  
 SUBMITTED BY DATE  
 PROJECT NO.  
 DRAWN BY DATE  
 CHECKED BY DATE  
 IN CHARGE BY DATE  
 NO. 3000

PROFILE  
 SUBMITTED BY DATE  
 PROJECT NO.  
 DRAWN BY DATE  
 CHECKED BY DATE  
 IN CHARGE BY DATE  
 NO. 3000