

ACNHF | ACBHF | ACNHF

ITEM NO.	ITEMS	UNIT	URBAN QUANTITY	ROADWAY	CULVERTS	LANDSCAPING	RETAINING WALLS	TRAFFIC SIGNALS						EMERGENCY VEHICLE PREEMPTION		RIGHT TURN LN (STA. 3167+50 TO STA. 3177+30)	SIDEWALK	
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	IL RT 59 @ BLACK ROAD	IL RT 59 @ VERTIN BLVD	IL RT 59 @ STA. 3122+00 LEFT	IL RT 59 @ THEODORE ST	IL RT 59 @ VERMETTE CIRCLE	IL RT 59 @ CATON FARM ROAD	INTERCONNECT	100% SHOREWOOD	100% JOLIET	100% JOLIET	50% STATE 50% SHOREWOOD
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	250	J000-2A	X028-2A	Y003	Y007	Y031-1F						Y031-3D		J000-1A	SFTY-1B	
60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	33,275	33,275														
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	636				636											
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3	3														
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	35	35														
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	148	148														
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	6	6														
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	8	8														
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	10	10														
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	10	10														
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	30	30														
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	4	4														
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	77	77														
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	5	5														
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1														
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	12	12														
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	9	9														
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	132	132														
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3														
60250200	CATCH BASINS TO BE ADJUSTED	EACH	6	6														
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3														
60251500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	1	1														
60255500	MANHOLES TO BE ADJUSTED	EACH	30	30														
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2														
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1														
60260050	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	2	2														
60260100	INLETS TO BE ADJUSTED	EACH	6	6														
60500040	REMOVING MANHOLES	EACH	32	32														
60500050	REMOVING CATCH BASINS	EACH	24	24														
60500060	REMOVING INLETS	EACH	37	37														
60600605	CONCRETE CURB, TYPE B	FOOT	2,059	2,059														
60601005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	136	136														
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	4,009	4,009														
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	41,433	41,433														
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	229	229														
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1,095	1,095														
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	8,741	8,741														
60619124	CONCRETE MEDIAN, TYPE SB-6 (SPECIAL)	SQ FT	16,430	16,430														
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	683	683														
60624600	CORRUGATED MEDIAN	SQ FT	7,195	7,195														
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1,600	1,600														
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4														
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	3	3														
63200310	GUARDRAIL REMOVAL	FOOT	1,764	1,764														

• SPECIALITY ITEM  
 \*\*100% SHOREWOOD QUANTITIES "NOT IDENTIFIED" IN FUNDING BREAKDOWNS NOTED ABOVE\*\*

REVISIONS	
NAME	DATE
REVISED IL59 ALIGN.	12/22/06

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 ILLINOIS ROUTE 59

DATE 3/18/08  
 DRAWN BY FA  
 CHECKED BY RCB

Rev 7-18-08

PLAN  
 DATE  
 BY  
 CHECKED  
 DATE  
 NO.

PROFILE  
 DATE  
 BY  
 CHECKED  
 DATE  
 NO.