F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	114R-1	WILL	355	10
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

	ITEM NO.	ITEMS	UNIT	URBAN QUANTITY	ACNHF ROADWAY	ACBHF CULVERTS	ACNHF ~~LANDSCAPING~~	ACNHF RETAINING WALLS	ACNHF TRAFFIC SIGNALS IL RT 59 @ BLACK ROAD	IL RT 59 @ VERTIN BLVD	IL RT 59 @ STA. 3122+00 LEFT	IL RT 59 @ THEODORE ST	IL RT 59 @ VERMETTE CIRCLE	IL RT 59 @ CATON FARM ROAD	INTERCONNECT	EMERGENCY VEHICLE PREEMPTION		RIGHT TURN LN (STA. 3167+50 TO STA. 3177+30)	SIDEWALK			
					80% FED 20% STATE	80% FED 20% STATE	~~80% FED 20% STATE~~	80% FED 20% STATE	80% FED 10% STATE 5% SHOREWOOD 5% WILL COUNTY	100% SHOREWOOD	100% JOLIET	80% FED 10% STATE 10% JOLIET	80% FED 10% STATE 10% JOLIET	80% FED 10% STATE 5% JOLIET 5% WILL COUNTY	80% FED 20% STATE	100% SHOREWOOD	100% JOLIET	100% JOLIET	50% STATE 50% SHOREWOOD	50% STATE 50% JOLIET		
					J000-2A	X028-2A	~~Y003~~	Y007	Y031-1F							Y031-3D		J000-1A	SFTY-1B			
●	X0323670	PREFORMED DETECTOR LOOP	FOOT	6,395					2,495	547	629	949	912	863								
	X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	8,284	8,284																	
	X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	8,284	8,284																	
	X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1,590		1,590																
●	X0323797	PAINT NEW TRAFFIC SIGNAL POST	EACH	5					4	1												
●	X0324232	PAINT NEW MAST ARM POLE, UNDER 40 FEET	EACH	2						2												
●	X0325096	OPTIMIZE TRAFFIC SIGNAL SYSTEM	L SUM	1											1							
●	X0325141	PAINT NEW MAST ARM POLE, 40 FEET AND OVER	EACH	6					4	2												
●	X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	5					2	1		1		1								
	X0545000	BOX CULVERT REMOVAL	FOOT	358	273	85																
	X0712400	TEMPORARY PAVEMENT	SQ YD	28,900	28,900																	
	X2111000	TOPSOIL EXCAVATION	CU YD	37,851	37,851																	
	X2800100	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	EACH	608	608																	
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	24	24																	
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	33	33																	
	X4023000	TEMPORARY ACCESS (ROAD)	EACH	20	20																	
	X4200500	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	2,290	2,290																	
	X4402100	PAVED DITCH REMOVAL	SQ YD	10	10																	
	X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	2	2																	
	X6050700	REMOVE INLET BOX	EACH	2	2																	
	X6065701	CONCRETE MEDIAN, TYPE SM-4.06	SQ FT	143	143																	
	X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	24	24																	
●	X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	6					1	1	1	1	1	1								
●	X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	15,405											15,405							
●	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 IC	FOOT	3,997					917	562	498	749	513	758								
●	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	2,204												694	1,510					
	X8900010	TEMPORARY TRAFFIC SIGNAL INTERCONNECT	EACH	2					1					1								
	XX000610	RELOCATE EXISTING MAILBOX	EACH	8	8																	
	XX001758	WOOD FENCE REMOVAL	FOOT	2,518	2,518																	
	XX001875	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	7	7																	
	XX002155	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	1	1																	
	XX004295	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 3V FRAME AND GRATE	EACH	1	1																	
	XX004394	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 3V FRAME AND GRATE	EACH	7	7																	
●	XX004913	REMOVE FIBER OPTIC CABLE FROM CONDUIT	FOOT	3,437											3,437							
	XX004990	CATCH BASINS TYPE C, TYPE 3V FRAME AND GRATE	EACH	4	4																	
	XX005656	INLET FILTER CLEANING	EACH	820	820																	
	XX006055	MANHOLES, TYPE A, 7' DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1																	
	XX006573	CATCH BASINS, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	EACH	1	1																	
	XX006574	CATCH BASINS, TYPE A, 6'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1																	
●	XX006661	UNINTERRUPTABLE POWER SUPPLY	EACH	6					1	1	1	1	1	1								
	XX172700	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1																	
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	143,180	143,180																	
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																	
NP	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	3	3																	

● SPECIALITY ITEM

~~** 100% SHOREWOOD QUANTITIES (NOT IDENTIFIED IN FUNDING BREAKDOWNS NOTED ABOVE)~~

NP= Non-Participating

REVISIONS	
NAME	DATE
REVISED IL59 ALIGN.	12/22/06

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

ILLINOIS ROUTE 59

DATE 3/18/08
DRAWN BY FA
CHECKED BY RCB

SCALE: NONE