

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	30	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62989

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	URBAN
				100% STATE
20200100	EARTH EXCAVATION	CU YD	207	207
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	42	42
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	174	174
25000210	SEEDING, CLASS 2A	ACRE	0.02	0.02
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10
25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	0.09	0.09
25100630	EROSION CONTROL BLANKET	SQ YD	542	542
44004250	PAVED SHOULDER REMOVAL	SQ YD	247	247
50300225	CONCRETE STRUCTURES	CU YD	7.8	7.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	6.4	6.4
50300300	PROTECTIVE COAT	SQ YD	33	33
50300510	RUSTICATION FINISH	SQ FT	70	70
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,430	1,430
63200310	GUARDRAIL REMOVAL	FOOT	76	76
66400550	CHAIN LINK FENCE, 4' (SPECIAL)	FOOT	1,010	1,010
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	1,010	1,010
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	253	253
X0324640	FLUTED KNEE WALL	FOOT	925	925
X2500322	SEEDING, CLASS 5A, (MODIFIED)	ACRE	0.09	0.09
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1

INDEX OF SHEETS

SHEET	DESCRIPTION
1	COVER SHEET
2	GENERAL NOTES AND PROJECT COMMITMENTS
3	SUMMARY OF QUANTITIES / INDEX / HIGHWAY STANDARDS
4	EXISTING AND PROPOSED TYPICAL SECTIONS
5-9	ALIGNMENT PLANS, SURVEY TIES AND CONTROL POINTS
10-13	EXISTING AND PROPOSED KNEE WALL PLANS
14-16	STRUCTURAL DETAILS
17	BD-51 DISTRICT 1, BENCHING DETAIL FOR EMBANKMENT WIDENING
18	TC-10 DISTRICT 1, TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS & DRIVEWAYS
19	TC-17 DISTRICT 1, TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES
20	TC-18 DISTRICT 1, SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS
21	TC-22 DISTRICT 1, ARTERIAL ROAD INFORMATION SIGN
22-30	CROSS SECTIONS

IDOT HIGHWAY STANDARDS

SHEET	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-01	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
664001-01	CHAIN LINK FENCE
701601-05	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701701-05	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-03	LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE, for speeds < 45 mph
701901	TRAFFIC CONTROL DEVICES
720001	SIGN PANEL MOUNTING DETAILS
720006-01	SIGN PANEL ERECTION DETAILS
728001	TELESCOPING STEEL SIGN SUPPORT
731001	BASE FOR TELESCOPING STEEL SIGN SUPPORT

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com



REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 94/90 (DAN RYAN EXPRESSWAY) NORTHBOUND KNEE WALLS (45TH ST TO 43RD ST)
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 04/25/08
DRAWN BY: JDC
CHECKED BY:

S00-1

5/11/08 PM 4/24/2008