

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	41	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
62995				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	URBAN
				100% STATE
				JOOO
20200100	EARTH EXCAVATION	CU YD	335	335
20900410	SAND BACKFILL	CU YD	6	6
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	44	44
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	291	291
25000210	SEEDING, CLASS 2A	ACRE	0.06	0.06
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	16	16
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	16	16
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	16	16
25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	0.11	0.11
25100630	EROSION CONTROL BLANKET	SQ YD	846	846
44004250	PAVED SHOULDER REMOVAL	SQ YD	230	230
50300225	CONCRETE STRUCTURES	CU YD	19	19
50300255	CONCRETE SUPERSTRUCTURE	CU YD	18	18
50300300	PROTECTIVE COAT	SQ YD	90	90
50300510	RUSTICATION FINISH	SQ FT	212	212
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3700	3700
60618324	CONCRETE MEDIAN SURFACE, 6" (SPECIAL)	SQ FT	339	339
63200310	GUARDRAIL REMOVAL	FOOT	39	39
66400550	CHAIN LINK FENCE, 4" (SPECIAL)	FOOT	1,535	1,535
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	1,540	1,540
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	385	385
X0324640	FLUTED KNEE WALL	FOOT	1,427	1,427
X2500322	SEEDING, CLASS 5A, (MODIFIED)	ACRE	0.11	0.11
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	24	24
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1

INDEX OF SHEETS

SHEET	DESCRIPTION
1	COVER SHEET
2	GENERAL NOTES AND PROJECT COMMITMENTS
3	SUMMARY OF QUANTITIES / INDEX / HIGHWAY STANDARDS
4	EXISTING AND PROPOSED TYPICAL SECTIONS
5-9	ALIGNMENT PLANS, SURVEY TIES AND CONTROL POINTS
10-16	EXISTING AND PROPOSED KNEE WALL PLANS
17-21	STRUCTURAL DETAILS
22	BD-51 DISTRICT 1, BENCHING DETAIL FOR EMBANKMENT WIDENING
23	TC-10 DISTRICT 1, TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS & DRIVEWAYS
24	TC-17 DISTRICT 1, TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES
25	TC-18 DISTRICT 1, SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS
26	TC-22 DISTRICT 1, ARTERIAL ROAD INFORMATION SIGN
27-41	CROSS SECTIONS

IDOT HIGHWAY STANDARDS

SHEET	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-01	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
664001-01	CHAIN LINK FENCE
701601-05	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701701-05	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-03	LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE, for speeds < 45 mph
701901	TRAFFIC CONTROL DEVICES
720001	SIGN PANEL MOUNTING DETAILS
720006-01	SIGN PANEL ERECTION DETAILS
728001	TELESCOPING STEEL SIGN SUPPORT
731001	BASE FOR TELESCOPING STEEL SIGN SUPPORT

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
SOUTHBOUND KNEE WALLS (47TH ST TO 43RD ST)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 04/25/08

DRAWN BY: JDC
CHECKED BY:

Rev. 7-18-08

S00-1

6/5/05 3 PM 4/24/2008