

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	03-00052-00-PV	LAKE	78	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NUMBER 63002				

EARTHWORK SCHEDULE				
LOCATION	EARTH EXCAVATION	EMBANKMENT NEEDED	EMBANKMENT NEEDED ADJUSTED FOR SHRINKAGE (15%)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
STAGE 1	6558	1560	1835	+ 4723
STAGE 2	3610	604	710	+ 2900
STAGE 3	2656	289	339	+ 2317

PIPE UNDERDRAIN SCHEDULE				
BEGIN UNDERDRAIN		SAG LOCATION	END UNDERDRAIN	
LT	RT		LT	RT
7+50.00	7+50.00	8+00.00	8+50.00	8+50.00
22+55.00	22+55.00	23+05.00	23+55.00	23+55.00
34+00.00	34+00.00	34+50.00	35+00.00	35+00.00
39+10.00	39+10.00	39+60.00	40+10.00	40+10.00
49+10.00	49+10.00	49+60.00	50+10.00	50+10.00
55+40.00	55+40.00	55+90.00	56+40.00	56+40.00
69+70.00	69+70.00	70+20.00	70+70.00	70+70.00
78+75.00	78+75.00	79+25.00	79+75.00	79+75.00
104+25.00	104+25.00	104+75.00 (LAKE ST.)	105+25.00	105+25.00

PLAN	SURVEYED	DATE
NOTE BOOK NO.	BY	

PROFILE	SURVEYED	DATE
NOTE BOOK NO.	BY	

REVISIONS	
NAME	DATE

VILLAGE OF GRAYSLAKE
 SHOREWOOD ROAD
 IL ROUTE 83 TO ROLLINS ROAD
 SCHEDULE OF QUANTITIES

SCALE:
 DATE: 11/06/07

DESIGNED BY: MTK
 DRAWN BY: MTK/BB/GP
 CHECKED BY: RPI