



F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00017-00-PV	KANE	232	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

SPECIALTY ITEMS	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	QUANTITY	80% FEDERAL 20% VILLAGE					YOGO 100% VILLAGE
					1000-2A	Y002 - TRAFFIC SIGNS	Y030 - /E HIGHWAY LIGHTING	Y031 - /F TRAFFIC SIGNALS	Y046 - BICYCLE & PEDESTRIAN FACILITY	
	73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	3		3				
	* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1994	1994					
	* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	30504	30504					
	* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	10591	10591					
	* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1446	1446					
	* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	520	520					
	* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	357	357					
	* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10					
	* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2					
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1730	1730					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	300	300					
	* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1			
	* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1			
	* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	2095				2095		
	* 81000700	CONDUIT IN TRENCH, 2-1/2" DIA., GALVANIZED STEEL	FOOT	596				596		
	* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	285			240	45		
	* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	235				235		
	* 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	20				20		
	* 81018500	CONDUIT, PUSHED 2" DIA., GALVANIZED STEEL	FOOT	359				359		
	* 81018600	CONDUIT, PUSHED 2-1/2" DIA., GALVANIZED STEEL	FOOT	238			190	48		
	* 81018900	CONDUIT, PUSHED 4" DIA., GALVANIZED STEEL	FOOT	1215			306	909		
	* 81400100	HANDHOLE	EACH	10				10		
	* 81400200	HEAVY-DUTY HANDHOLE	EACH	7				7		
	* 81400300	DOUBLE HANDHOLE	EACH	4				4		
	* 81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	4469			4469			
	81701345	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C NO. 3/0	FOOT	280			280			
	* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	800			800			
	* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3715			500	3215		
	* 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	4			4			
	* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	22			18			
	* 82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1			1			
	* 83050730	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 8 FT. DAVIT ARM	EACH	8			8			
	* 83050800	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 12 FT. MAST ARM	EACH	14			14			
	* 83057220	LIGHT POLE, WOOD, 40 FOOT, CLASS 4	EACH	2			2			
	* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	180			180			
	* 83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	40			40			
	* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	22			22			
	* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	2			2			
	* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	2			2			
	* 84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	6			6			
	* 84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	8			8			
	* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1			1			
	* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1			1			
	* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1			1			
	* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1				1		

PLAN	DATE
BY	
SURVEYED	
PLOTTED	
PRINTED	
NOTE BOOK	
NO.	

PROFILE	DATE
BY	
SURVEYED	
PLOTTED	
PRINTED	
NOTE BOOK	
NO.	

REVISIO 7/11/08

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p style="text-align: center;">SUMMARY OF QUANTITIES</p> <p>SCALE: NTS DATE: 02/07/08</p> <p>DRAWN BY: CHECKED BY: WBR</p>