CONTRACT NO. 63023

Engineering Enterprises, Inc.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00017-00-PV	KANE	232	10
STA.		TO STA.		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

SPECIALTY ITEMS	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	QUANTITY	80 % FEDERAL 20% VILLAGE						Y060 100% VILLAGE
					1000-2A	Y002 - TRAFFIC SIGNS	Y030 - /E HIGHWAY LIGHTING	Y031 - /E TRAFFIC SIGNALS	Y046 - BICYCLE & PEDESTRIAN FACILITY	Y080 - TRAINING	
	XX003919	FLAGPOLE RELOCATION	L SUM	1	1						
	XX004096	REMOVE AND RE-INSTALL CONCRETE FLARED END SECTIONS	EACH	7	7						
*	XX004731	CONNECTION TO EXISTING WATERMAIN	EACH	4							4
*	XX004907	GATE VALVE 12" WITH VAULT, 5' DIAMETER	EACH	8							8
*	X0325705	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1				1			
	XX005084	LIGHTING CONTROLLER FOUNDATION	EACH	1			1				
	XX005106	PVC CASING PIPE, 18"	FOOT	25							25
*	XX005401	STEEL CASING PIPE 24" (BORED AND JACKED)	FOOT	365							365
*	X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	2				2			
*	XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	20			20				
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	34,661	34,661						
	Z0002750	BARRICADES, TYPE III	EACH	9	9						
	Z0076600	TRAINEES	HOUR	5,000						5,000	
*	XX007558	GATE VALVE 6" WITH VAULT, 4' DIAMETER	EACH	1							1
*	XX007559	GATE VALVE 8" WITH VAULT, 4' DIAMETER	EACH	1							1
*	XX007560	SANITARY SEWER, PVC SDR-21, 10"	FOOT	815							815
*	XX007561	SANITARY SEWER, PVC SDR-21, 12"	FOOT	545							545
	XX007562	SIGN REMOVAL, SPECIAL	L SUM	1		1					
	X0324879	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	4	4						
*	XX007563	TEMPORARY LUMINAIRE, SODIUM VAPOR HORIZONTAL MOUNT 310 WATT WITH PHOTOCELL	EACH	4			4				
*	XX007564	TEMPORARY LUMINAIRE, SODIUM VAPOR HORIZONTAL MOUNT 400 WATT WITH PHOTOCELL	EACH	4			4				
*	XX007565	POLYETHYLENE DUCT BORED AND PULLED, 1 1/4" DIA WITH ELECTRIC CABLE 600 V (EPR-TYPE RHW) 3-1/C NO. 6 AND 1/C NO. 6 GROUND	FOOT	5,350			5,350				
	XX007566	STORM SEWER REMOVAL AND REINSTALLATION, 15"	FOOT	25	25						
*	X8950100	RELOCATE EXISTING MASTER CONTROLLER	EACH	2				2			
*	86400100	TRANSCEIVER - FIBER OPTIC	EACH	1				1			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS

DRAWN BY:

DATE: 02/07/08

CHECKED BY: WBR

REVISED 7/11/08

PLAN: SURVEYED / PLOTTED / ALIGNMENT CHECKED / RT. OF WAY CHECKED / CADD FILE NAME / NOTE BOOK NO. / BY / DATE

PROFILE: SURVEYED / PLOTTED / GRADES CHECKED / B.M. NOTED / STRUCTURE NOTATIONS CHKD / NOTE BOOK NO. / BY / DATE

Plotted: July 11, 2008 @ 11:55 AM By: Kris Pung – Tab: 10 SUMQ-6 (22x34)

Path: H:\SDSKPROJ\SG0548\DWG\SG0732\DWG FINAL ENG\CONTRACT 63E-SG0546-SUMQ