



F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00017-00-PV	KANE	232	5
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

SPECIALTY ITEMS	PAY ITEM				80 % FEDERAL 20% VILLAGE					
	NUMBER	PAY ITEM DESCRIPTION	UNITS	QUANTITY	1000-2A	Y002 - TRAFFIC SIGNS	Y030 -/E HIGHWAY LIGHTING	Y031 -/F TRAFFIC SIGNALS	Y046 - BICYCLE & PEDESTRIAN FACILITY	Y080 - TRAINING
										Y060 100% VILLAGE
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	198	198					
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	75	75					
	20200100	EARTH EXCAVATION	CU YD	27455	27455					
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	186	186					
	20700300	POROUS GRANULAR EMBANKMENT, SPECIAL	TON	100	100					
	20800150	TRENCH BACKFILL	CU YD	1946	882					1064
	21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	1688	1688					
	25000110	SEEDING, CLASS 1A	ACRE	7	7					
	25000200	SEEDING, CLASS 2	ACRE	7	7					
	25000314	SEEDING, CLASS 4B	ACRE	1	1					
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1286	1286					
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1286	1286					
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1286	1286					
	25100125	MULCH, METHOD 3	ACRE	15	15					
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4080	4080					
	28000300	TEMPORARY DITCH CHECKS	EACH	18	18					
	28000400	PERIMETER EROSION BARRIER	FOOT	12926	12926					
	28000500	INLET AND PIPE PROTECTION	EACH	9	9					
	28000510	INLET FILTERS	EACH	73	73					
	28100105	STONE RIPRAP, CLASS A3	SQ YD	124	124					
	28200200	FILTER FABRIC	SQ YD	124	124					
	31101600	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	913	246				667	
	35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	5864	5864					
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13579	13579					
	40600300	AGGREGATE (PRIME COAT)	TON	20	20					
	40600895	CONSTRUCTING TEST STRIP	EACH	4	4					
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1034	1034					
	40600990	TEMPORARY RAMPS	SQ YD	150	150					
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	3329	3329					
	40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	11410	11410					
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	75					75	
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2493	2493					
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	7146	7146					
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	338	338					
	44000100	PAVEMENT REMOVAL	SQ YD	1285	1285					
	44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	3733	3733					
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	24625	24625					
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	180	180					
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1621	1621					
	44000600	SIDEWALK REMOVAL	SQ FT	2870	2870					
	44003100	MEDIAN REMOVAL	SQ FT	2658	2658					
	44004250	PAVED SHOULDER REMOVAL	SQ YD	2581	2581					
	44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	52	52					
	44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	26	26					
	44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	56	56					
	48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	5812	5812					

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS

DATE: 02/07/08

DRAWN BY:

CHECKED BY: WBR

PLAN	SURVEYED	BY	DATE
	ALLOTTED		
	NOTED		
	RT. OF WAY CHECKED		
NO.	FILE NAME		

PROFILE	SURVEYED	BY	DATE
	ALLOTTED		
	NOTED		
	STRUCTURE NOTATION OK'D		
NO.			