



F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00017-00-PV	KANE	232	6
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

SPECIALTY ITEMS	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	QUANTITY	80 % FEDERAL 20% VILLAGE						
					1000-2A	Y002 - TRAFFIC SIGNS	Y030 - /E HIGHWAY LIGHTING	Y031 - /F TRAFFIC SIGNALS	Y046 - BICYCLE & PEDESTRIAN FACILITY	Y080 - TRAINING	Y060 100% VILLAGE
	50105220	PIPE CULVERT REMOVAL	FOOT	327	327						
	50300225	CONCRETE STRUCTURES	CJ YD	189	189						
	50800105	REINFORCEMENT BARS	POUND	14670	14670						
	54001000	BOX CULVERT END SECTIONS	EACH	4	4						
	54010302	PRECAST CONCRETE BOX CULVERT 3' X 2'	FOOT	145	145						
	54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	215	215						
	542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	40	40						
	542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	24	24						
	54206739	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE, EQUIVALENT ROUND-SIZE 24"	FOOT	144	144						
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	16	16						
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	5	5						
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2						
	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1						
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	2565	2565						
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	553	553						
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	521	521						
	550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	131	131						
	550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	639	639						
	550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	285	285						
	550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	68	68						
	550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	262	262						
	550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	187	187						
	550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	FOOT	468	468						
	55100500	STORM SEWER REMOVAL 12"	FOOT	60	60						
	55100700	STORM SEWER REMOVAL 15"	FOOT	45	45						
	55100900	STORM SEWER REMOVAL 18"	FOOT	282	282						
*	56103000	DUCTILE IRON WATER MAIN 6"	FOOT	31							31
*	56103100	DUCTILE IRON WATER MAIN 8"	FOOT	30							30
*	56103300	DUCTILE IRON WATER MAIN 12"	FOOT	3596							3596
*	56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1							1
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	265	265						
	60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	15	15						
	60107600	PIPE UNDERDRAIN 4"	FOOT	1322	1322						
	60108100	PIPE UNDERDRAIN 4" (SPECIAL)	FOOT	180	180						
	60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	2	2						
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	11	11						
	60207915	CATCH BASINS, TYPE C, TYPE 11V FRAME AND GRATE	EACH	11	11						
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	6	6						
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	12	12						
	60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	3	3						
	60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2						
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5						

PLAN	DATE
BY	
REVIEWED	
PLOTTED	
ALIGNMENT CHECKED	
GRADES CHECKED	
NOTE BOOK NO.	
FILE NAME	

PROFILE	DATE
BY	
REVIEWED	
PLOTTED	
GRADES CHECKED	
NOTE BOOK NO.	
FILE NAME	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS
DATE: 02/07/08

DRAWN BY:
CHECKED BY: WBR