

**Engineering Enterprises, Inc.**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00017-00-PV	KANE	232	7
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

**SUMMARY OF QUANTITIES**

SPECIALTY ITEMS	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	QUANTITY	80 % FEDERAL 20% VILLAGE						
					1000 - 2A	Y002 - TRAFFIC SIGNS	Y030 - /E HIGHWAY LIGHTING	Y031 - /F TRAFFIC SIGNALS	Y046 - BICYCLE & PEDESTRIAN FACILITY	Y080 - TRAINING	Y060 100% VILLAGE
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
	60228110	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6							6
	60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	11	11						
	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	13	13						
	60240312	INLETS, TYPE B, TYPE 11V FRAME AND GRATE	EACH	5	5						
	60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	8	8						
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	7	7						
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2						
	60255500	MANHOLES TO BE ADJUSTED	EACH	1	1						
	60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	4						
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3	3						
	60500050	REMOVING CATCH BASINS	EACH	1	1						
	60500060	REMOVING INLETS	EACH	4	4						
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3728	3728						
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	5819	5819						
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	17929	17929						
	60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	11044	11044						
	61100605	MISCELLANEOUS CONCRETE	CU YD	5	5						
	61101007	STORM SEWERS PROTECTED, CLASS A, 6"	FOOT	50	50						
	61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	50	50						
	61101011	STORM SEWERS PROTECTED, CLASS A, 10"	FOOT	50	50						
	61133100	FIELD TILE JUNCTION VAULT 2'	EACH	5	5						
	61139900	STORM SEWER (SPECIAL) 6"	FOOT	50	50						
	61140000	STORM SEWER (SPECIAL) 8"	FOOT	50	50						
	61140100	STORM SEWER (SPECIAL) 10"	FOOT	50	50						
*	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	438	438						
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2						
	67100100	MOBILIZATION	L SUM	1	1						
	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1						
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	60						
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	32	30			2			
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5220	5220						
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1706	1706						
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	39264	39264						
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	9513	9513						
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1289	1289						
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	401	401						
	70300320	PAVEMENT MARKING TAPE, TYPE I 4"	FOOT	750	750						
	70300360	PAVEMENT MARKING TAPE, TYPE I 12"	FOOT	320	320						
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	860	860						
	72000100	SIGN PANEL - TYPE 1	SQ FT	455		327		128			
	72000200	SIGN PANEL - TYPE 2	SQ FT	32		32					
	72000300	SIGN PANEL - TYPE 3	SQ FT	378		378					
	72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1		1					
	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	810		810					

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: NTS  
DATE: 02/07/08

DRAWN BY:  
CHECKED BY: WBR

PLAN

SURVEYED GRADES CHECKED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

ALIGNED CHECKED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

NOTE BOOK NO. \_\_\_\_\_

FILE NO. \_\_\_\_\_

PROFILE

SURVEYED GRADES CHECKED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

NOTED BY: \_\_\_\_\_

NO. \_\_\_\_\_

STRUCTURE NOTATION: \_\_\_\_\_