



F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	06-00017-00-PV	KANE	232	27
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

DRAINAGE SCHEDULE

PIPE #	D.S. STR.	U.S. STR.	PIPE DIA. (IN)	LENGTH (FT)	SLOPE %	TRENCH BACKFILL CY	SS CL A TY 12" FOOT	SSRG CLA TY1 12" FOOT	PIPE CULVERT CL A TY 1 12" FOOT	SS CL A TY 15" FOOT	SSRG CLA TY1 15" FOOT	SS CL A TY 1 18" FOOT	SSRG CLA TY 1 18" FOOT	SS CL A TY 1 21" FOOT	SS CL A TY 1 24" FOOT	SSRG CLA TY1 24" FOOT	PIPE CULVERT CL A TY 1 24ERS" FOOT	PIPE CULVERT CL A TY 1 36ERS" FOOT	SS CL A TY 1 36" FOOT	CLASS D PATCH TYPE 2 6" SQ YD	CLASS D PATCH TYPE 2 15" SQ YD	
802	801	802	24	151	0.68										151							
803	802	803	24	24	0.71	5.4										24						
803A	803	803A	15	8	1.25					8												
803B	803A	803B	12	11	4.29	1.8	11															
803C	803A	803C	12	13	3.75	2.1	13															
803D	803A	803D	15	70	0.68	13.2			70													
803E	803D	803E	12	12	1.33	1.7	12															
803F	803D	803F	15	25	0.52	2.5			25													
804	803	804	21	131	0.59								131									
804A	804	804A	18	9	0.77							9										
804B	804E	804B	12	9	2.92	6.7	9															
804C	804A	804C	18	84	0.52	13.5						84										
804D	804C	804D	18	19	0.68	2.9						19										
804E	804	804E	18	56	0.67							56										
805	804E	805	18	94	0.62							94										
805A	805	805A	12	8	0.83		8															
805B	805A	805B	12	58	0.49	13.1	58															
805C	805B	805C	12	31	0.45	6.0	31															
806	805	806	15	108	0.36				108													
806A	806	806A	12	8	1.25		8															
806B	806A	806B	12	27	0.50	5.5	27															
806C	806A	806C	12	58	1.23	13.7	58															
806D	806C	806D	12	34	0.42	6.2	34															
1100A	1100	1100A	12	36	0.51	2.5	36															
1101A	1101	1101A	15	36	0.60	2.0			36													
1101B	1101A	1101B	12	36	0.51	0.5	36															
1102A	1102	1102A	12	31	0.59	6.5	31															
1103A	1103	1103A	12	70	1.04	13.4	70															
1103B	1103A	EXIST	12	40	0.45	5.5	40															
1104A	EXIST	1104A	12	36	0.47	5.0	36															
1105A	EXIST	1105A	12	9	1.09	1.9	9															
1106	1106	EXIST	24ERS	24	0.67	4.0											24					
1106A	EXIST	1106A	24ERS	48	0.69	4.1											48					
1107	1107	EXIST	24ERS	24	0.67	3.8											24					
1107A	EXIST	1107A	24ERS	48	0.69	3.9											48					
1109	1109	EXIST	36ERS	16	1.00															16		
1109A	EXIST	1109A	36ERS	8	0.25															8		
1111	EXIST	1111	12	40	1.72				40													
1200A	1200	1200A	24	22	0.33	1.6									22							
1201A	1201	1201A	12	9	1.25		9															
1202A	1202	1202A	12	35	0.50	3.3	35															
1203A	1203	1203A	12	4	1.09		4															
<b>SUBTOTAL</b>						152.3	575.0	0.0	40.0	247.0	0.0	262.0	0.0	131.0	173.0	24.0	144.0	24.0	0.0	0.0	0.0	

DATE	
BY	
DATE	
BY	
DATE	
BY	
DATE	
BY	
DATE	
BY	
DATE	
BY	

DATE	
BY	
DATE	
BY	
DATE	
BY	
DATE	
BY	
DATE	
BY	
DATE	
BY	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: NTS		DRAWN BY:
DATE: 02/07/08		

DRAINAGE SCHEDULE

Plotted: May 27, 2008 @ 2:52 PM By: Kris Pung - Tab: 27 SCH-2 (22x34)

Path: \\S:\P\PROJ\630546\DWG\630732\DWG\FINAL ENG\CONTRACT B\6-630546-SCHEDS