

F. A. U. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2947	08-00148-00-RS	COOK	011	005
STA.		TO STA.		
FED. ROAD DIST. NO.	LINE	FED. RD PROJECT		

CONTRACT #63044

LOCATION OF SIDEWALK OR DRIVEWAY REMOVAL AND REPLACEMENT						
Stataline Road from Michigan City Road to 155th St						
Approx. Location	West	East	Driveway R & R Area (Sq Yds)	Sidewalk R & R Area (Sq Ft)	Delectable Warning (Sq Ft)	Reason
Bit. Drive at Sta. 25+10 Stataline.	X		8			Curb Removal and Replacement
Bit. Drive at Sta. 25+45 Stataline.	X		5			Curb Removal and Replacement
Bit. Drive at Sta. 25+65 Stataline.	X		7.6			Curb Removal and Replacement
STA. 26+70 TO STA. 27+35	X			325		Curb Removal and Replacement
STA. 28+27	X			40		Curb Removal and Replacement
STA. 28+48	X			8		Curb Removal and Replacement
STA. 29+18 TO STA. 29+52	X			34		Curb Removal and Replacement
SW corner of Bit. alley at Sta. 30+08	X			36	8	Handicap Ramp Installation
NW corner of Bit. alley at sta. 30+08	X			36	8	Handicap Ramp Installation
STA. 30+62	X			39		Curb Removal and Replacement
Conc. Drive at Sta. 31+00 Stataline.	X		12			Curb & Gutter Removal and Replacement
Bit. Drive at Sta. 31+12 Stataline.	X		7.3			Curb & Gutter Removal and Replacement
STA. 31+85	X			32.5		Curb Removal and Replacement
SW corner of stone alley at sta. 33+62	X			24	8	Handicap Ramp Installation
NW corner of stone alley at Sta. 33+82 TO Sta. 35+50	X			858	16	Handicap Ramp Installation & Curb Removal and Replacement
Conc. Drive at Sta. 34+22 Stataline.	X		8			Curb & Gutter Removal and Replacement
NW corner of Highland (Sta. 35+50)	X			36	8	Handicap Ramp Installation & Curb Removal and Replacement
Sta. 36+41 TO Sta. 36+87.5	X			270	8	Handicap Ramp Installation & Curb Removal and Replacement
Sta. 37+15 TO Sta. 37+75	X			360		Curb Removal and Replacement
SW corner of Elizabeth	X			162	8	Handicap Ramp Installation & Curb Removal and Replacement
NW corner of Elizabeth	X			35	8	Handicap Ramp Installation
SW corner of alley (Sta. 40+08)	X			36	8	Handicap Ramp Installation
NW corner of alley (Sta. 40+08)	X			24	8	Handicap Ramp Installation
STA. 40+50	X			60		Curb Removal and Replacement
Conc. Drive at Sta. 40+50 Stataline.	X		6.7			Curb & Gutter Removal and Replacement
STA. 42+08 TO STA. 43+01	X			558		Curb Removal and Replacement
SW corner of alley (Sta. 43+35)	X			30	8	Handicap Ramp Installation & Curb Removal and Replacement
Alley @ Sta. 43+35 to Ruth (Sta. 45+00)	X			936	16	Handicap Ramp Installation & Curb Removal and Replacement
NW corner of Ruth	X			36	8	Handicap Ramp Installation
SW corner of alley (Sta. 46+40)	X			36	8	Handicap Ramp Installation & Curb Removal and Replacement
Conc. Drive at Sta. 46+85 Stataline.	X		14.7			Curb & Gutter Removal and Replacement
NW corner of alley (Sta. 46+55) TO Sta. 47+38	X			300	8	Handicap Ramp Installation & Curb Removal and Replacement
STA. 47+95 TO STA. 48+00	X			30		Curb Removal and Replacement
SW corner of Mason	X			9	8	Handicap Ramp Installation
NW corner of Mason to alley at Sta. 49+70	X			750	16	Handicap Ramp Installation & Curb Removal and Replacement
Conc. Drive at Sta. 49+50 Stataline.	X		5.3			Curb & Gutter Removal and Replacement
Alley @ Sta. 49+70 to Warren	X			792	16	Handicap Ramp Installation & Curb Removal and Replacement
NW corner of Warren to Sta. 52+80	X			798	8	Handicap Ramp Installation & Curb Removal and Replacement
SW corner of driveway at Sta. 52+95	X			36	8	Handicap Ramp Installation
NW corner of Driveway at Sta. 52+95	X			36	8	Handicap Ramp Installation
SW corner of Webb	X			16	8	Handicap Ramp Installation
NW corner of Webb	X			20	8	Handicap Ramp Installation
SW corner of driveway at Sta. 56+15	X			30	8	Handicap Ramp Installation
NW corner of driveway at Sta. 56+15	X			25	8	Handicap Ramp Installation
SW corner of 157th	X			16	8	Handicap Ramp Installation
NW corner of 157th	X			16	8	Handicap Ramp Installation
STA. 58+00 TO STA. 58+15	X			75		Curb & Gutter Removal and Replacement
STA. 58+95 TO STA. 59+88	X			415		Curb & Gutter Removal and Replacement
Bit. Drive at Sta. 59+33 Stataline.	X		5.6			Curb & Gutter Removal and Replacement
SW corner of 156th PL	X			50	8	Handicap Ramp Installation
NW corner of 156th PL	X			16	8	Handicap Ramp Installation
Sta. 61+14 to Sta. 61+24	X			48		Curb & Gutter Removal and Replacement
NW corner of 156th ST	X			25	8	Handicap Ramp Installation
Sta. 64+62 to Sta. 67+00	X			644		Curb & Gutter Removal and Replacement
Sta. 67+57 to Sta. 69+90	X			2006		Curb & Gutter Removal and Replacement
Total			80.2	10164.5	272	

LOCATION OF CURB REMOVAL AND REPLACEMENT					
Stataline Road from Michigan City Road to 155th Street					
Approx. Location	West	East	Curb R & R Length (Ft)	Curb & Gutter R & R Length (Ft)	
STA. 24+16 TO STA. 26+80	X		164		
STA. 26+00 TO STA. 27+35	X		135		
STA. 28+05 TO STA. 28+35	X		30		
STA. 29+18 TO STA. 30+00	X		94		
STA. 30+20 TO STA. 31+57	X		150		
STA. 32+85	X		8		
STA. 33+88 TO STA. 35+20	X		144		
STA. 35+50	X		36		
STA. 38+41 TO STA. 38+78	X		51		
STA. 37+15 TO STA. 37+75	X		60		
SW CORNER OF ELIZABETH	X		32		
NW CORNER OF ELIZABETH	X		8		
SW CORNER OF ALLEY (STA. 40+08)	X		10		
NW CORNER OF ALLEY (STA. 40+08)	X		10		
STA. 40+45 TO STA. 40+55	X		10		
STA. 42+08 TO STA. 43+01	X		93		
SW CORNER OF ALLEY (STA. 43+35)	X		9		
ALLEY @ STA. 43+35 TO RUTH (STA. 45+00)	X		146		
NW CORNER OF RUTH	X		10		
SW CORNER OF ALLEY (STA. 48+40)	X		8		
NW CORNER OF ALLEY (STA. 48+55) TO STA. 47+38	X		78		
STA. 47+95 TO STA. 48+00	X		5		
SW CORNER OF MASON	X		7		
NW CORNER OF MASON TO ALLEY AT STA. 49+70	X		146		
ALLEY @ STA. 49+70 TO WARREN	X		148		
NW CORNER OF WARREN TO STA. 52+80	X		135		
SW CORNER OF DRIVEWAY AT STA. 52+95	X		10		
SW CORNER OF WEBB	X		10		
NW CORNER OF WEBB	X		10		
STA. 58+00 TO STA. 58+15	X		15		
STA. 59+95 TO STA. 59+88	X		83		
SW CORNER OF 156TH PL	X		10		
NW CORNER OF 156TH PL	X		10		
STA. 61+10	X		10		
NW CORNER OF 156TH ST	X		10		
STA. 64+62 TO STA. 67+00	X		238		
STA. 67+57 TO STA. 69+90	X		236		
Total			1737	642	

REMOVAL WORK AT EXISTING INTERSECTIONS					
Stataline Road from Michigan City Road to 155th Street					
Location	West	East	Work at Intersection		
Stataline Road			North of River Oaks Drive Butt Joint Required		
Michigan City Road	x		Grind along existing EOP line (No Butt Joint)		
Wildwood		x	Grind along existing EOP line (No Butt Joint)		
Detroit		x	Grind along existing EOP line (No Butt Joint)		
Highland	x		Butt Joint Required		
Highland		x	Grind along existing EOP line (No Butt Joint)		
Elizabeth	x		Butt Joint Required		
Elizabeth		x	Grind along existing EOP line (No Butt Joint)		
Waltham		x	Grind along existing EOP line (No Butt Joint)		
Ruth	x		Butt Joint Required		
Ruth		x	Grind along existing EOP line (No Butt Joint)		
Mason	x		Butt Joint Required		
Mason		x	Grind along existing EOP line (No Butt Joint)		
Warren	x		Butt Joint Required		
Warren		x	Grind along existing EOP line (No Butt Joint)		
Webb	x		Butt Joint Required		
Webb		x	Grind along existing EOP line (No Butt Joint)		
157th Street	x		Butt Joint Required		
156th Place		x	Butt Joint Required		
156th Street	x		Butt Joint Required		

LOCATION OF HOT-MIX ASPHALT PARKWAY REMOVAL AND SIDEWALK REPLACEMENT					
Stataline Road from Michigan City Road to 155th St					
Approx. Location	West	East	Bit Parkway Rem Area (Sq Yds)	Sidewalk Replacement, 5" Area (Sq Ft)	Reason
Sta. 64+95 to Sta. 66+70	X		25	225	Curb Removal and Replacement
Sta. 66+00 to Sta. 66+40	X		13.3	120	Curb Removal and Replacement
Sta. 67+57 to Sta. 68+72	X		38.3	345	Curb Removal and Replacement
Sta. 68+85 to Sta. 69+35	X		16.7	150	Curb Removal and Replacement
Total			93.3	640	

LOCATION OF DRAINAGE STRUCTURE ADJUSTMENTS						
Stataline Road from Michigan City Road to 155th Street						
Approx. Location	Catch Basin Remove & Replace	Adjustment Open Lid	Adjustment Closed Lid	Domestic Water Open Lid	Water Valve Service Box Adjusted	Water Valve Adjustment
STA. 25+75, LT						
STA. 27+45, LT			1			1
STA. 27+45, LT						1
STA. 30+23, LT			1			
STA. 40+50, LT			1			
STA. 44+80, LT			1			
STA. 45+10, LT			1			
STA. 46+70, LT			1			
STA. 49+80, LT	1					
STA. 49+85, LT			1			
STA. 50+05, LT						1
STA. 51+35, RT			1			
STA. 58+05, LT	1					
STA. 60+88, LT						1
STA. 61+05, LT					1	
STA. 61+14, LT			1			
STA. 61+14, LT			1			
STA. 61+35, LT			1			
STA. 63+83, LT						1
STA. 63+92, LT			1			
STA. 64+07, LT					1	
STA. 64+07, LT			1			
STA. 64+25, LT			1			
STA. 64+26, LT	1					
STA. 67+09, LT			1			
STA. 67+17, LT						1
STA. 67+48, LT			1			
STA. 67+59, LT	1					
STA. 67+59, LT			1			
STA. 68+40, LT					1	
Total	4	8	9	0	4	5

STATELINE ROAD PAVEMENT MARKING SCHEDULE				
FROM MICHIGAN CITY ROAD TO 155TH STREET AVENUE				
LOCATION	24" STOP BAR (WHITE)	4" DOUBLE YELLOW	4" SKIP DASH (YELLOW)	6" CROSSWALK (WHITE)
Station 5+20 LT				
Station 5+20 to Station 6+00, 10 FT LT		80	1720	
Station 6+00 to Station 22+00, CL			290	
Station 22+00 to Station 33+60, CL				
Station 33+60 to Station 35+07, CL		294		
Station 35+07 LT		17		
Station 35+60 LT		18		
Station 35+60 to Station 36+25, CL			130	
Station 36+25 to Station 55+75, CL				488
Station 55+75 to Station 57+44, CL			336	
Station 57+44 RT		17		
Station 57+83 LT		19		
Station 57+83 to Station 59+50, CL			734	
Station 59+50 to Station 70+08, CL				265
Station 64+28.5				140
Total	71	1576	690.8	140

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STATELINE ROAD ROADWAY RESURFACING SCHEDULES

SCALE: VERT. NA
HORIZ. NA
DATE 04/23/08

DRAWN BY RG
CHECKED BY RW

ROBINSON ENGINEERING, LTD.
17000 SOUTH PARK AVENUE, SOUTH HOLLAND, ILLINOIS 60473
(708) 381-8700 FAX (708) 381-3885
ILLINOIS DESIGN FIRM REGISTRATION NO. 15400128

08003_60-SCHD-01