

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1177	(110,111)T	LEE	59	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	BOX FED. 20% STATE Y007 TOTAL QUANTITY
50100300	REMOVAL OF EXISTING STRUCTURES NO.1	EACH	1
50100400	REMOVAL OF EXISTING STRUCTURES NO.2	EACH	1
50100500	REMOVAL OF EXISTING STRUCTURES NO.3	EACH	1
50100600	REMOVAL OF EXISTING STRUCTURES NO.4	EACH	1
50104400	CONCRETE HEADWALL REMOVAL	EACH	3
50300225	CONCRETE STRUCTURES	CU YD	15
50800105	REINFORCEMENT BARS	POUND	3290
51500100	NAME PLATES	EACH	4
54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH	2
54001002	BOX CULVERT END SECTION, CULVERT NO.2	EACH	1
54001003	BOX CULVERT END SECTION, CULVERT NO.3	EACH	4
54010604	PRECAST CONCRETE BOX CULVERT 6' X 4'	FOOT	98
54010804	PRECAST CONCRETE BOX CULVERT 8' X 4'	FOOT	98
54011005	PRECAST CONCRETE BOX CULVERT 10' X 5'	FOOT	63
54205917	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL, EQUIVALENT ROUND-SIZE 42"	FOOT	112
54207609	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ARCH, EQUIVALENT ROUND-SIZE 54"	FOOT	198
54215157	STEEL END SECTIONS, EQUIVALENT ROUND-SIZE 42"	EACH	4
54213450	END SECTIONS 15"	EACH	2
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	68
60100925	PIPE DRAINS 8"	FOOT	50
60100945	PIPE DRAINS 12"	FOOT	20
60100955	PIPE DRAINS 15"	FOOT	60
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	400

*SPECIALTY ITEMS

PLOT DATE = Tue Feb 26 13:49:32 2008
 FILE NAME = c:\prowork\proj\6428187\6428187.dgn
 PLOT SCALE = 0.25"=1'-0"
 USER NAME = cameron