F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1177	(110,111)T	LEE	59	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

54001003 BOX CULVERT END SECTION, CULVERT NO. 3

LOCATION		EACH
STA 528+47	LT & RT	4
	TOTAL	4

54010604 PRECAST CONCRETE BOX CULVERT 6' X 4'

LOCATION		FOOT
STA 28+64		98
	TOTAL	98

54010804 PRECAST CONCRETE BOX CULVERT 8' X 4'

LOCATION		FOOT
STA 528+47		98
	TOTAL	98

54011005 PRECAST CONCRETE BOX CULVERT 10' X 5'

LOCATION		FOOT
STA 261+52		63
	TOTAL	63

54205917 PIPE CULVERTS, TYPE 1, CORRUGATED STEEL, EQUIVALENT ROUND-SIZE 42"

LOCATION		FOOT
STA 325+10	LT	56
STA 326+50	LT	56
	TOTAL	112

54207609 PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE, ARCH, EQUIVALENT ROUND-SIZE 54"

LOCATION		FOOT
STA 277+15		198
	TOTAL	198

542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"

LOCATION		FOOT
STA 328+60	31' RT	68
	TOTAL	68

54213450 END SECTIONS 15"

LOCATION		EACH
STA 328+58	LT & RT	2
	TOTAL	2

54215157 STEEL END SECTIONS, EQUIVALENT ROUND-SIZE 42"

LOCATION		EACH
STA 325+10	LT	2
STA 326+50	LT	2
	TOTAL	4

60100925 PIPE DRAINS 8"

LOCATION		FOOT
STA 261+52	LT	50
	TOTAL	50

60100945 PIPE DRAINS 12"

LOCATION		FOOT
STA 277+15	LT	20
	TOTAL	20

60100955 PIPE DRAINS 15"

LOCATION		FOOT
STA 261+52	LT	60
	TOTAL	60

61100500 EXPLORATION TRENCH 52" DEPTH

LOCATION		FOOT
STA 28+64	LT & RT	200
STA 261+52	LT	100
STA 276+90	LT	100
	TOTAL	400

61101020 STORM SEWERS PROTECTED, CLASS A, 18"

LOCATION		FOOT
STA 28+64	LT & RT	160
	TOTAL	160

61133100 FIELD TILE JUNCTION VAULTS 2' DIA.

LOCATION		EACH
STA 261+52	LT	3
STA 276+90	LT	1
	TOTAL	4

61133200 FIELD TILE JUNCTION VAULTS 3' DIA.

LOCATION		EACH
STA 28+64	LT & RT	2
	TOTAL	2

63200310 GUARDRAIL REMOVAL

LOCATION			FOOT
STA 28+00.85	TO	29+28.46 LT	127.61
STA 28+00.53	TO	29+15.53 RT	115
STA 260+03.75	TO	262+68.6 RT	264.9
STA 260+47.10	TO	263+12.7 LT	265.67
STA 275+72.66	TO	278+47.81RT	275.15
STA 275+78.94	TO	278+54.3 LT	275.38
		TOTAL	1323.71

63500105 DELINEATORS

LOCATION		EACH
STA 28+64	LT & RT	2
STA 261+52	LT & RT	2
STA 277+15	LT & RT	2
STA 528+47	LT & RT	2
	TOTAL	8

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY-MARKERS

LOCATION		EACH
STA 27+25	40' LT	1
STA 27+50	40' RT	1
STA 28+35	75' RT	1
STA 28+40	85' LT	1
STA 28+80	85' LT	1
STA 28+90	75' RT	1
STA 29+25	40' RT	1
STA 29+40	40' LT	1
STA 259+25	39.83' LT	1
STA 259+50	40' RT	1
STA 260+00	55' LT	1
STA 261+25	80' RT	1
STA 261+75	60' LT	1
STA 262+20	80' RT	1
STA 262+20	40' LT	1
STA 263+30	40' RT	1
STA 275+35	40' RT	1
STA 277+50	90' RT	1
STA 279+00	90' RT	1
STA 279+40	40' RT	1
STA 323+25	60' LT	1
STA 324+50	75' LT	1
STA 325+50	75' LT	1
STA 328+50	40' LT	1
STA 527+00	40' LT & RT	2
STA 527+90	60' RT	1
STA 528+30	80' LT	1
STA 528+85	80' LT	1
STA 529+10	60' RT	1
STA 529+75	40' LT & RT	2
	TOTAL	32

78001110 PAINT PAVEMENT MARKING - LINE 4"

LOCATION						FOOT
STA 28+34	TO	28+94	WHITE	EOP	(2 Apl.)	240
STA 28+34	TO	28+94	YELLOW	SKIP DASH	(2 Apl.)	30
STA 261+11	TO	261+93	WHITE	EOP	(2 Apl.)	328
STA 261+11	TO	261+93	YELLOW	SKIP DASH	(2 Apl.)	41
STA 276+63.69	TO	277+66.0	WHITE	EOP	(2 Apl.)	409
STA 276+63.69	TO	277+66.0	YELLOW	SKIP DASH	(2 Apl.)	51
STA 328+28.24	TO	328+44.2	WHITE	EOP	(2 Apl.)	64
STA 328+28.24	TO	328+44.2	WHITE	SKIP DASH	(2 Apl.)	8
STA 528+13.50	TO	528+80.5	WHITE	EOP	(2 Apl.)	268
STA 528+13.50	TO	528+80.5	YELLOW	SKIP DASH	(2 Apl.)	34
STA 1198+69.65	TO	1999+66.7	YELLOW	ISLAND	(2 Apl.)	392
DETOUR ROUTE / PER SPECIAL PROVISION						45307
					TOTAL	47172

78001150 PAINT PAVEMENT MARKING - LINE 12"

LOCATION						FOOT
STA 1198+69.65	TO	1999+66.7	YELLOW	ISLAND	(2 Apl.)	32
					TOTAL	32

78001180 PAINT PAVEMENT MARKING - LINE 24"

LOCATION				FOOT
STA 28+34	WHITE	STOP BAR	(2 Apl.)	44
STA 28+34	WHITE	STOP BAR	(2 Apl.)	24
			TOTAL	68

X0323660 DROP BOX NO.1

LOCATION		EACH
STA 28+64	RT	1
	TOTAL	1

X0323661 DROP BOX NO.2

LOCATION		EACH
STA 261+52	LT	1
	TOTAL	1

X0323662 DROP BOX NO.3

LOCATION		EACH
STA 277+15	LT	1
	TOTAL	1

Z0023600 FILLING EXISTING CULVERTS

LOCATION		EACH
STA 328+36.24		1
	TOTAL	1

PLOT DATE = Tue Feb 26 10:26:59 2008
FILE NAME = c:\projects\c280107\c280107cvr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = cushmanbw