

60300105 FRAMES AND GRATES TO BE ADJUSTED

EACH	LOCATION	
	STA	
1.00	162 + 00	RIGHT, GORE AREA
TOTAL =	1.00	

64200105 SHOULDER RUMBLE STRIP

FOOT	LOCATION	
	STA to STA	
8,350.00	95 + 25 178 + 75	LEFT SHOULDER
375.00	95 + 25 99 + 00	RIGHT SHOULDER
1,280.00	110 + 00 122 + 80	RIGHT SHOULDER
2,365.00	131 + 65 155 + 30	RIGHT SHOULDER
875.00	170 + 00 178 + 75	RIGHT SHOULDER
TOTAL =	13,245.00	

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION	
	STA to STA	
4" WHITE SKIP DASH		
1500.00	59 + 48 89 + 25	MAINLINE, 2 APPLICATIONS
4500.00	89 + 25 179 + 25	MAINLINE, 2 APPLICATIONS
87.50		REST AREA ON RAMP, 2 APPLICATIONS
62.50		SCALE OFF RAMP, GORE, 2 APPLICATIONS
95.00		SCALE ON RAMP, GORE, 2 APPLICATIONS
4" WHITE SOLID		
5954.00	59 + 48 89 + 25	RIGHT EDGE LINE, 2 APPLICATIONS
450.00		REST AREA ON RAMP GORE, 2 APPLICATIONS
2120.00		REST AREA ON RAMP EDGE OF PAVT, 2 APPLICATIONS
2430.00	110 + 60 122 + 75	MAINLINE, EDGE OF PAVT, 2 APPLICATIONS
1850.00		SCALE OFF RAMP, EDGE OF PAVT, 2 APPLICATIONS
320.00		SCALE OFF RAMP, GORE, 2 APPLICATIONS
4450.00	132 + 75 155 + 00	MAINLINE, EDGE OF PAVT, 2 APPLICATIONS
630.00		SCALE ON RAMP GORE, 2 APPLICATIONS
590.00		SCALE ON RAMP EDGE OF PAVT, 2 APPLICATIONS
1380.00	172 + 35 179 + 25	MAINLINE, EDGE OF PAVT, 2 APPLICATIONS
4" YELLOW SOLID		
18000.00	89 + 25 179 + 25	MAINLINE, 2 APPLICATIONS
TOTAL =	44,419.00	

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION	
	STA to STA	
4" WHITE SKIP DASH		
250.00	59 + 48 89 + 25	MAINLINE
750.00	89 + 25 179 + 25	MAINLINE
14.58		REST AREA ON RAMP
10.42		SCALE OFF RAMP, GORE
15.83		SCALE ON RAMP, GORE
4" WHITE SOLID		
992.33	59 + 48 89 + 25	MAINLINE
75.00		REST AREA ON RAMP GORE
353.33		REST AREA ON RAMP EDGE OF PAVT
405.00	110 + 60 122 + 75	MAINLINE, EDGE OF PAVT
308.33		SCALE OFF RAMP, EDGE OF PAVT
53.33		SCALE OFF RAMP, GORE
741.67	132 + 75 155 + 00	MAINLINE, EDGE OF PAVT
105.00		SCALE ON RAMP GORE
98.33		SCALE ON RAMP EDGE OF PAVT
230.00	172 + 35 179 + 25	MAINLINE, EDGE OF PAVT
4" YELLOW SOLID		
3000.00	89 + 25 179 + 25	MAINLINE
TOTAL =	7,403.17	

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	
	STA to STA	
YELLOW - SOLID		
600	89 + 25 92 + 25	2 APPLICATIONS, MAINLINE, LEFT EDGE LINE
16950	95 + 25 180 + 00	2 APPLICATIONS, MAINLINE, LEFT EDGE LINE
subtotal	17550	
WHITE - SOLID		
1764	59 + 48 68 + 30	2 APPLICATIONS, MAINLINE, RIGHT EDGE LINE
1250	78 + 75 85 + 00	2 APPLICATIONS, MAINLINE, RIGHT EDGE LINE
1700	90 + 00 98 + 50	2 APPLICATIONS, MAINLINE, RIGHT EDGE LINE
2700	110 + 50 124 + 00	2 APPLICATIONS, MAINLINE, RIGHT EDGE LINE
3800	135 + 00 154 + 00	2 APPLICATIONS, MAINLINE, RIGHT EDGE LINE
1650	171 + 75 180 + 00	2 APPLICATIONS, MAINLINE, RIGHT EDGE LINE
subtotal	12864	
TOTAL =	30,414.00	

78001130 PAINT PAVEMENT MARKING - LINE 6"

FOOT	LOCATION	
	STA to STA	
WHITE - SKIP		
6050	59 + 00 180 + 00	2 APPLICATIONS, CENTERLINE SKIP-DASH
TOTAL =	6,050.00	

78001140 PAINT PAVEMENT MARKING - LINE 8"

FOOT	LOCATION	
	STA to STA	
WHITE - SKIP		
88	70 + 25 72 + 00	RAMP MERGE AREA, 2 APPLICATIONS
168	100 + 00 103 + 35	RAMP MERGE AREA, 2 APPLICATIONS
488	155 + 10 164 + 85	RAMP MERGE AREA, 2 APPLICATIONS
subtotal	744	
WHITE - SOLID		
800	86 + 00 90 + 00	2 APPLICATIONS, MAINLINE, OFF-RAMP GORE AREA
450	86 + 00 88 + 00	2 APPLICATION, EXIT-RAMP
230	98 + 85 100 + 00	ENTRANCE-RAMP, 2 APPLICATION
1050	129 + 75 135 + 00	2 APPLICATIONS, MAINLINE, OFF-RAMP GORE AREA
680	129 + 85 133 + 00	2 APPLICATION, EXIT-RAMP
320	153 + 50 155 + 10	ENTRANCE-RAMP, 2 APPLICATION
subtotal	3530	
TOTAL =	4,274.00	

78001150 PAINT PAVEMENT MARKING - LINE 12"

FOOT	LOCATION	
	STA to STA	
WHITE - SOLID		
400.00	86 + 00 89 + 50	2 APPLICATION, EXIT-RAMP
40.00	130 + 00 131 + 25	2 APPLICATION, WEIGH SCALE OFF-RAMP
TOTAL =	440.00	

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION	
	STA to STA	
153.00	59 + 00 180 + 00	ONE-WAY CRYSTAL @ 80 FOOT CENTERS
TOTAL =	153.00	

Z0029200 GRINDING PORTLAND CEMENT CONCRETE SURFACE

SQ YD	LOCATION	
	STA to STA	
733.33	89 + 25 92 + 00	BOTH LANES, 1 1/2" REMOVAL
TOTAL =	733.33	

FILE NAME = P:\1-88 resurfconvr.dgn

USER NAME = grantpm
 PLOT SCALE = 50,000' / IN.
 PLOT DATE = Thu May 15 11:03:27 2008

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES				
SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	*	ROCK ISLAND	31	17
CONTRACT NO. 64D34				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				