

STATION	REMARKS	LENGTH OF PATCH		PARTIAL DEPTH REMOVAL X4401705		PARTIAL DEPTH PATCHING X4421000		SEVERITY	CL D PATCH T3 44201843	CL D PATCH T4 44201845	SUB MAT, A 31100100
		LT LANE (feet)	RT LANE (feet)	LT LANE (yd ²)	RT LANE (yd ²)	LT LANE (ton)	RT LANE (ton)		16" (SQ YD)	16" (SQ YD)	12" (ton)
169 + 75			26		34.7		9.7				
170 + 46			10		13.3		3.7	X			
171 + 24			6		8.0		2.2				
171 + 55			6		8.0		2.2	X			
171 + 80			74		98.7		27.6	XX			
172 + 30		30		40.0		11.2		X			
172 + 66			6		8.0		2.2				
173 + 16		27		36.0		10.1					
173 + 57			6		8.0		2.2				
173 + 88			19		25.3		7.1				
174 + 43			10		13.3		3.7				
174 + 84		45		60.0		16.8					
175 + 67			6		8.0		2.2				
175 + 88		97		129.3		36.2		X			
176 + 07			30		40.0		11.2	X			
176 + 96			6		8.0		2.2				
177 + 10		34		45.3		12.7		X			
177 + 25			15		20.0		5.6				
177 + 42											
177 + 60			20		26.7		7.5				
177 + 73											
178 + 21		6		8.0		2.2					
		SUB-TOTAL =		1920.0	3792.0	537.6	1061.8				
CONTINGENCIES				249.6	644.6	69.9	180.5		99.09	330.31	293.4
TOTAL				6606		1849.7			99.1	330.3	293.4

NOTE: EXISTING OVERLAY FAILURE SEVERITY RATINGS

- LOW
- X MODERATE
- XX MEDIUM
- XXX HIGH

FILE NAME = P:\1-80 resurfvr.dgn	USER NAME = grantpm	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE	F.A.I. RTE. 80	SECTION *	COUNTY ROCK ISLAND	TOTAL SHEETS 31	SHEET NO. 21		
PLOT SCALE = 50.000' / IN.	CHECKED -	REVISED -	SCALE:			SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT
PLOT DATE = Thu May 15 11:03:28 2008	DATE -	REVISED -	CONTRACT NO. 64D34									