

SUMMARY OF QUANTITIES

SFTY-2A
100% STATE

Pay Code	Description	Unit	Total Quantity	SN 008-0028	SN 071-0069	SN 089-0060
50102400	CONCRETE REMOVAL	CU YD	34	18	12	4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	34	18	12	4
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,640	2,550	1,520	570
50800515	BAR SPLICERS	EACH	71	38	22	11
52000110	PREFORMED JOINT STRIP SEAL	FOOT	255	135	90	30
63300405	REMOVAL AND REINSTALLATION OF EXISTING TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	10	4	4	2
67100100	MOBILIZATION	L SUM	1	0.4	0.3	0.3
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1			1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	4	2	2	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	15	6	9	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1800	960	840	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	8805	3360	1895	3550
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	60	24	36	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2965	1125	650	1190
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1000	512.5	312.5	175
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2000	1025	625	350
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	9500	2700	1600	5200
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	140		140	
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	120		120	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1675	750	525	400
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	5	2	2	1
* Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	10	4	4	2

* SPECIALTY ITEM

* Various
** (106BR)M, (4B-2)M & 177-4B-3)M