

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	1000 80% FED. 20% STATE TOTAL QUANTITY
21400100	GRADING AND SHAPING DITCHES	FOOT	1500
35101400	AGGREGATE BASE COURSE, TYPE B	TON	308
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	61.0
40600300	AGGREGATE (PRIME COAT)	TON	165.7
40600535	LEVELING BINDER (HAND METHOD), N70	TON	20
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	6321
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1039
40600990	TEMPORARY RAMP	SQ YD	172
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	801
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	8737
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1171
42001200	PAVEMENT FABRIC	SQ YD	982
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	873
44002228	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 7"	SQ YD	2,042
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	256
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	47
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	35
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	173
44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	75
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SQ YD	982
44213200	SAW CUTS	FOOT	2955
48101200	AGGREGATE SHOULDERS, TYPE B	TON	10242
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	2
60107700	PIPE UNDERDRAINS 6"	FOOT	5025
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	37

CODE NUMBER	PAY ITEM	UNIT	1000 80% FED. 20% STATE TOTAL QUANTITY
60260100	INLETS TO BE ADJUSTED	EACH	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	200
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12146
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2048
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	216
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	106113
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	75
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	858
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	100
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	534
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	534
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0017100	DOWEL BARS	EACH	680
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	1566
Z0028700	GRANULAR SUBGRADE REPLACEMENT	CU YD	261
Z0040315	PILOT CAR	DAY	5
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1
Z0075300	TIE BARS	EACH	329

* SPECIALTY ITEMS

REVISED 7/17/08

