

PAINT PAVEMENT MARKING LINE, 4" TEMPORARY PAVEMENT MARKING LINE, 4"				
LOCATION		SIDE	SINGLE SOLID	SHORT TERM
FROM	TO	(LT/RT/CL)	FOOT	FOOT
174+85	250+57	RT	7572.0	
174+85	250+57	LT	7572.0	
180+00	189+12	RT-CL	912.0	
191+40	199+00	LT-CL	760.0	
229+90	240+05	RT-CL	1015.0	
251+87	259+24	LT	737.0	
251+87	305+75	RT	5388.0	
260+54	305+75	LT	4521.0	
276+45	287+10	LT-CL	1065.0	
304+25	311+43	RT-CL	718.0	
307+05	342+32	RT	3527.0	
342+32	343+90	RT	158.0	
343+90	358+85	RT	1495.0	
307+05	342+32	LT	3527.0	
342+32	343+90	LT	158.0	
343+90	358+85	LT	1495.0	
314+20	320+55	LT-CL	635.0	
321+85	330+20	RT-CL	835.0	
332+00	339+85	LT-CL	785.0	
360+15	465+00	RT	10485.0	
360+15	465+00	LT	10485.0	
445+55	454+95	RT-CL	940.0	
466+30	518+25	RT	5195.0	
466+30	518+25	LT	5195.0	
470+00	478+20	LT-CL	820.0	
479+88	485+60	RT-CL	572.0	
488+86	494+40	LT-CL	554.0	
505+80	516+75	RT-CL	1095.0	
519+15	524+85	LT-CL	570.0	
519+55	557+69	RT	3814.0	
519+55	557+93	LT	3838.0	
559+16	564+78	RT	562.0	
559+40	564+90	LT	550.0	
561+59	566+59	RT-CL	500.0	
577+39	624+65	RT	4726.0	
577+39	624+65	LT	4726.0	
577+39	582+39	LT-CL	500.0	
595+68	603+10	RT-CL	742.0	
606+70	614+30	LT-CL	760.0	
625+95	678+26	RT	5231.0	
625+95	678+26	LT	5231.0	
679+36	679+58	RT	22.0	
679+36	679+58	LT	22.0	
SUBTOTAL			104830.0	
LOCATION		SIDE	DOUBLE SOLID	SHORT TERM
FROM	TO	(LT/RT/CL)	FOOT	FOOT
240+05	276+45	CL	7,280.0	330.9
454+95	470+00	CL	3,010.0	136.8
478+20	479+88	CL	336.0	15.3
516+75	519+15	CL	480.0	21.8
SUBTOTAL			11,106.0	505.0
TOTAL			115,936.0	505.0

PAINT PAVEMENT MARKING LINE, 6" TEMPORARY PAVEMENT MARKING LINE, 6"				
LOCATION		SIDE	SKIPDASH 10'	SHORT TERM
FROM	TO	(LT/RT/CL)	FOOT	FOOT
174+85	180+00	CL	128.8	46.8
180+00	189+12	CL	228.0	82.9
189+12	191+40	CL	57.0	20.7
191+40	199+00	CL	190.0	69.1
199+00	229+90	CL	772.5	280.9
229+90	240+05	CL	253.8	92.3
276+45	287+10	CL	266.3	96.8
287+10	304+25	CL	428.8	155.9
304+25	311+43	CL	179.5	65.3
311+43	314+20	CL	69.3	25.2
314+20	320+55	CL	158.8	57.7
320+55	321+85	CL	32.5	11.8
321+85	330+20	CL	208.8	75.9
330+20	332+00	CL	45.0	16.4
332+00	339+85	CL	196.3	71.4
339+85	342+32	CL	61.8	22.5
342+32	343+90	CL	39.5	14.4
343+90	445+55	CL	2541.3	924.1
445+55	454+95	CL	235.0	85.5
470+00	478+20	CL	205.0	74.5
479+88	485+60	CL	143.0	52.0
485+60	488+86	CL	81.5	29.6
488+86	494+40	CL	138.5	50.4
494+40	505+80	CL	285.0	103.6
505+80	516+75	CL	273.8	99.5
519+15	524+85	CL	142.5	51.8
524+85	557+81	CL	824.0	299.9
559+28	566+59	CL	182.8	73.1
577+39	582+60	CL	130.3	52.1
582+60	595+60	CL	325.0	118.2
595+60	603+10	CL	187.5	68.2
603+10	606+70	CL	90.0	32.7
606+70	614+30	CL	190.0	69.1
614+30	679+58	CL	1632.0	593.5
TOTAL			10,924.0	3983.8

PAINT PAVEMENT MARKING LINE, 24"			
LOCATION		SIDE	LENGTH
FROM	TO	(LT/RT/CL)	FOOT
251+23	251+38	RT	15.0
251+23	251+92	LT	69.0
259+89	260+02	LT	13.0
306+40	306+54	RT	14.0
306+40	306+55	LT	15.0
359+50	359+62	RT	12.0
359+50	359+64	LT	14.0
465+65	465+79	RT	14.0
465+65	465+80	LT	15.0
518+90	519+03	LT	13.0
518+90	519+07	RT	17.0
625+30	625+42	RT	12.0
625+30	625+43	LT	13.0
678+71	678+83	RT	12.0
678+71	678+85	LT	14.0
TOTAL			262.0

THERMOPLASTIC PAVEMENT MARKING LINE, 4" TEMPORARY PAVEMENT MARKING LINE, 4"				
LOCATION		SIDE	SINGLE SOLID	SHORT TERM
FROM	TO	(LT/RT/CL)	FOOT	FOOT
120+50	126+15	RT	565.0	
120+50	168+78	LT	4828.0	
127+45	136+78	RT	933.0	
138+08	168+78	RT	3070.0	
138+75	145+76	LT-CL	701.0	
159+40	168+75	RT-CL	935.0	
170+08	174+85	RT	477.0	
170+08	174+85	LT	477.0	
170+15	174+85	LT-CL	470.0	
575+78	577+39	RT	161.0	
575+78	577+39	LT	161.0	
SUBTOTAL			12,778.0	
LOCATION		SIDE	DOUBLE SOLID	SHORT TERM
FROM	TO	(LT/RT/CL)	FOOT	FOOT
120+50	138+75	CL	3,650.0	182.5
168+75	170+15	CL	280.0	12.7
566+59	568+99	RT	480.0	21.8
566+59	568+99	LT	480.0	21.8
568+99	570+49	RT	300.0	13.6
568+99	570+49	LT	300.0	13.6
570+49	571+49	LT	200.0	9.1
572+49	573+49	RT	200.0	9.1
573+49	574+99	RT	300.0	13.6
573+49	574+99	LT	300.0	13.6
574+99	577+39	LT	480.0	21.8
574+99	577+39	RT	480.0	21.8
SUBTOTAL			7,450.0	355.0
TOTAL			20,228.0	355.0

TEMPORARY PAVEMENT MARKING LINE, 6"				
LOCATION		SIDE	SKIPDASH 10'	SHORT TERM
FROM	TO	(LT/RT/CL)	FOOT	FOOT
138+75	145+76	CL	175.3	63.7
145+76	159+40	CL	341.0	124.0
159+40	168+75	CL	233.8	85.0
170+15	174+85	CL	117.5	42.7
TOTAL			868.0	315.4

THERMOPLASTIC PAVEMENT MARKING LINE, 8" TEMPORARY PAVEMENT MARKING LINE, 8"					
LOCATION		SIDE	SINGLE DASH	SINGLE SOLID	SHORT TERM
FROM	TO		FOOT	FOOT	FOOT
568+99	570+49	LANE LINE	38.0		
570+49	571+49	LANE LINE		100.0	10.0
572+49	573+49	LANE LINE		100.0	10.0
573+49	574+99	LANE LINE	38.0		
TOTALS			76.0	200.0	20.0

THERMOPLASTIC PAVEMENT MARKING LINE, 12" TEMPORARY PAVEMENT MARKING LINE, 12"					
LOCATION		WIDTH	LENGTH		
FROM	TO		FROM	TO	FOOT
566+59	568+99	0	12	102	
568+99	570+49	12	0	64	
573+49	574+99	0	12	64	
574+99	577+39	12	0	102	
TOTAL					331

THERMOPLASTIC PAVT MARK LINE, 24"			
LOCATION		SIDE	LENGTH
FROM	TO	(LT/RT/CL)	FOOT
126+80	127+04	RT	24.0
137+43	137+58	RT	15.0
169+43	169+58	LT	15.0
169+43	169+60	RT	17.0
565+44	565+59	RT	15.0
571+74	571+99	LT	25.0
571+99	572+27	RT	28.0
TOTAL			139.0

THERMOPLASTIC PAVEMENT MARKING LTR&SYM TEMPORARY PAVEMENT MARKING LTR&SYM			
LOCATION	TYPE	AREA	SHORT TERM
STATION		SQ FT	FOOT
570+73	TURN ARROW	15.6	48
571.25	TURN ARROW	15.6	48
572+73	TURN ARROW	15.6	48
573+25	TURN ARROW	15.6	48
TOTAL		62.4	192

NOTE:
FOR SHORT-TERM PAVEMENT MARKING ASSUME 3 APPLICATIONS