

SCHEDULE OF QUANTITIES

TABULATION OF CLASS A PATCHES, 11 INCH

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA		SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (each)	PATCHING REINFORCEMENT 44213000 (sq. yd)
					TYPE I 11" (sq. yd)	TYPE II 11" (sq. yd)			
662+80.39	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
663+64.87	NORTHBOUND	DL	10	6	0.0	6.7	44.0	0	6.7
665+60.23	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
666+28.87	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
666+55.27	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
666+81.67	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
669+29.83	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
669+56.23	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
671+67.43	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
674+57.83	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
675+89.83	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
686+93.35	NORTHBOUND	DL	6	12	0.0	8.0	60.0	0	8.0
687+61.99	NORTHBOUND	DL	12	6	0.0	8.0	48.0	0	8.0
688+46.47	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
688+57.03	NORTHBOUND	DL	12	6	0.0	8.0	48.0	0	8.0
688+67.59	NORTHBOUND	DL	12	6	0.0	8.0	48.0	0	8.0
688+99.27	NORTHBOUND	DL	10	6	0.0	6.7	44.0	0	6.7
691+05.19	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
691+26.31	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
692+42.47	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
697+65.19	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
698+07.43	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
698+23.27	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
698+44.39	NORTHBOUND	DL	10	6	0.0	6.7	44.0	0	6.7
709+63.75	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
709+95.43	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
718+98.31	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
727+00.87	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
727+21.99	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
728+11.75	NORTHBOUND	DL	6	6	4.0	0.0	36.0	0	4.0
SHEET TOTALS					92.0 (sq. yd)	52.0 (sq. yd)	1164.0 (ft)	0.0 (Each)	144.0 (sq. yd)