

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	RURAL	URBAN
				1000	1000
X4422048	PARTIAL DEPTH REMOVAL 5"	SO YD	366	366	
20200100	EARTH EXCAVATION	CU YD	511	511	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	46	46	
20400800	FURNISHED EXCAVATION	CU YD	1002	1002	
25000200	SEEDING, CLASS 2	ACRE	1.3	1.3	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	116	116	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	116	116	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	116	116	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	3	3	
25100115	MULCH, METHOD 2	ACRE	1.3	1.3	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	129	129	
28000300	TEMPORARY DITCH CHECKS	EACH	5	5	
28000400	PERIMETER EROSION BARRIER	FOOT	250	250	
28100107	STONE RIPRAP, CLASS A4	SO YD	26		26
28200200	FILTER FABRIC	SO YD	26		26
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SO YD	113	113	
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SO YD	1291	1291	
35501314	HOT-MIX ASPHALT BASE COURSE, 7 1/2"	SO YD	1291	1291	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	204	204	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9982	9343	639
40600300	AGGREGATE (PRIME COAT)	TON	219	206	13
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	4128	3860	268
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	200	200	
40600990	TEMPORARY RAMP	SO YD	319	229	90
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	148	148	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	9029	8492	537
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	174	174	
44000100	PAVEMENT REMOVAL	SO YD	1152	1152	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	20563	17818	2745
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	78060	74413	3647
44000400	GUTTER REMOVAL	FOOT	1812	1812	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	155	155	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	267	267	

SUMMARY OF QUANTITIES (Cont'd)			100% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	RURAL	URBAN
				1000	1000
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SO YD	4	4	
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	573	556	17
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	73	73	
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	56	56	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2119	2047	72
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SO YD	1532	1532	
60602500	CONCRETE GUTTER, TYPE A	FOOT	770	770	
60602800	CONCRETE GUTTER, TYPE B	FOOT	1387	1387	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	187.5	187.5	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	404	404	
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	50	50	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	4	4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10	
67100100	MOBILIZATION	L SUM	1	0.9	0.1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	7	7	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13632	12936	696
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	136922	131424	5498
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1515	1438	77
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	136922	131424	5498
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	25	25	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	656	627	29
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6	6	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1	
X4421000	PARTIAL DEPTH PATCHING	TON	102	102	

* Specialty Items