

PAVEMENT MARKING SCHEDULE

STATION TO STATION			LENGTH	PAINT PAVEMENT MARKING - LINE 4" WHITE	PAINT PAVEMENT MARKING - LINE 4" YELLOW	TEMPORARY PAVEMENT MARKING - LINE 4"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	PAINT PAVEMENT MARKING - LINE 24"
			FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	EACH	FOOT
RURAL										
456+57.00	TO	472+32.00	1575.0	3273.5	393.8	3667.3	468.0	52.0	20.0	25.0
472+32.00	TO	478+96.00	664.0	1328.0	830.0	2158.0	204.0	22.7	8.0	
478+96.00	TO	481+47.00	251.0	502.0	62.8	564.8	72.0	8.0	3.0	
481+47.00	TO	486+76.00	529.0	1058.0	661.3	1719.3	156.0	17.3	7.0	
486+76.00	TO	487+98.21	122.2	244.4	30.6	275.0	36.0	4.0	2.0	
487+98.21	BK=	488+04.32 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
488+04.32	TO	502+14.00	1409.7	2819.4	352.4	3171.8	420.0	46.7	18.0	
502+14.00	TO	507+95.77	581.8	1163.5	727.2	1890.8	180.0	20.0	7.0	
507+95.77	TO	509+81.00	185.2	370.5	231.5	602.0	60.0	6.7	5.0	
509+81.00	TO	520+66.39	1085.4	2170.8	2170.8	4341.6	324.0	36.0	27.0	
520+66.39	BK=	521+03.00 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
521+03.00	TO	533+81.40	1278.4	2556.8	2556.8	5113.6	384.0	42.7	32.0	
533+81.40	TO	551+11.00	1729.6	3459.2	3459.2	6918.4	516.0	57.3	22.0	
551+11.00	TO	556+69.00	558.0	1116.0	697.5	1813.5	168.0	18.7	7.0	
556+69.00	TO	559+65.00	296.0	592.0	74.0	666.0	84.0	9.3	4.0	
559+65.00	TO	562+95.12	330.1	660.2	412.7	1072.9	96.0	10.7	4.0	
562+95.12	BK=	563+31.58 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
563+31.58	TO	568+73.00	541.4	1082.8	676.8	1759.6	168.0	18.7	7.0	
568+73.00	TO	569+68.00	95.0	190.0	190.0	380.0	24.0	2.7	1.0	
569+68.00	TO	579+58.00	990.0	1980.0	1237.5	3217.5	300.0	33.3	12.0	
579+58.00	TO	584+19.00	461.0	922.0	115.3	1037.3	144.0	16.0	6.0	
584+19.00	TO	589+53.00	534.0	1068.0	667.5	1735.5	156.0	17.3	7.0	
589+53.00	TO	601+48.50	1195.5	2391.0	2391.0	4782.0	360.0	40.0	15.0	
601+48.50	BK=	309+00.00 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
309+00.00	TO	261+62.00	4738.0	9476.0	9476.0	18952.0	1416.0	157.3	59.0	
261+62.00	TO	253+23.00	839.0	1678.0	1048.8	2726.8	252.0	28.0	10.0	
253+23.00	TO	233+38.00	1985.0	3970.0	496.3	4466.3	600.0	66.7	25.0	
233+38.00	TO	227+89.00	549.0	1098.0	686.3	1784.3	168.0	18.7	7.0	
227+89.00	BK=	227+89.00 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
227+89.00	TO	226+29.00	132.3	264.7	165.4	430.1	36.0	4.0	2.0	
226+29.00	TO	224+49.00	180.0	360.0	45.0	405.0	60.0	6.7	2.0	
224+49.00	TO	217+67.00	682.0	1364.0	852.5	2216.5	204.0	22.7	9.0	
217+67.00	TO	196+50.00	2117.0	4234.0	529.3	4763.3	636.0	70.7	26.0	
196+50.00	BK=	196+50.00 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
196+50.00	TO	189+86.37	421.4	842.7	105.3	948.1	132.0	14.7	11.0	
189+86.37	TO	184+49.47	536.9	1073.8	134.2	1208.0	156.0	17.3	7.0	
184+49.47	TO	180+62.87	386.6	773.2	96.7	869.9	120.0	13.3	10.0	
180+62.87	TO	150+27.46	3035.4	6070.8	758.9	6829.7	912.0	101.3	38.0	

FILE NAME = c:\projects\74057\d\shetch_74057.dgn	USER NAME = swartzrw	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 20.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 5/14/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NA SHEET NO. 1 OF 7 SHEETS STA. TO STA.

F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2793	(O,P,Y)RS-1	FAYETTE	52	13
CONTRACT NO. 74057				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				