SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80% FED. 20% STATE 1000	CONSTRUCTION TYPE CODE 50% STATE 50% SHELBYVILLE Y025
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5016	4931	85
40600300	AGGREGATE (PRIME COAT)	TON	101	99	2
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2107	2071	36
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	560	560	
40600990	TEMPORARY RAMP	SQ YD	288	288	
40600995	TEMPORARY RAMP, SPECIAL	SQ YD	3210	3210	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	4213	4142	71
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	87	87	
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	13235	13235	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	36976	36126	850
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	5	5	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	22	22	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	547	547	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	766	766	
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	550	550	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	733	733	
66700095	PERMANENT SURVEY MARKERS	EACH	1	1	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7245	7245	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1607	1607	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	31980	31604	376

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80% FED. 20% STATE 1000	CONSTRUCTION TYPE CODE 50% STATE 50% SHELBYVILLE Y025
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2689	2689	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	104	104	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	201	201	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	599	599	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1607	1607	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	31980	31604	376
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2689	2689	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	104	104	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	201	201	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	458	458	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	12	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1617	1617	
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	3	3	

*Specialty Items

FILE NAME = c:\projects\74227d\shtsoq_74227.dgn	USER NAME = steffonnk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P RTE. 325	SECTION (12)RS-7	COUNTY SHELBY	TOTAL SHEETS 34	SHEET NO. 3
		DRAWN -	REVISED -					CONTRACT NO. 74227		
	PLOT SCALE = 20.0000 ' / IN.	CHECKED -	REVISED -							
	PLOT DATE = 5/7/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		