

PAVING SCHEDULE

STATION TO STATION	LENGTH	PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SURFACE COURSE, MIX "D", N90	LEVELING BINDER (MACHINE METHOD), N90	HMA SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL, 1/2	HMA SURFACE REMOVAL, 2 1/4	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP (SPECIAL)	TEMPORARY RAMP
	FEET	FEET	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	SQ YD	TON	SQ YD	SQ YD
906+45.00 TO 941+39.00	3494.0	28	10870	1087.0	21.7	913.1	456.5	280.0	10870.2		628.9		84.0
941+39.00 TO 965+32.00	2393.00	VARIABLE	-	OMIT WALMART									
965+32.00 TO 972+91.99	760.0	28	2364	236.4	4.7	198.6	99.3	280.0	2364.4		136.8		84.0
972+91.99 TO 974+28.02	136.0	-	-	OMIT BRIDGE									
974+28.02 TO 1011+02.50	3674.5	36	14698	1469.8	29.4	1234.6	617.3			14697.9		1391.6	54.0
1011+02.50 TO 1012+09.00	106.5	36 - 48	497	49.7	1.0	41.7	20.9			497.0		83.1	
1012+09.00 TO 1014+41.00	232.0	48	1237	123.7	2.5	103.9	52.0			1237.3		211.1	
1014+41.00 TO 1015+24.00	83.0	48 - 36	387	38.7	0.8	32.5	16.3			387.3		24.4	
1015+24.00 TO 1046+71.00	3147.0	36	12588	1258.8	25.2	1057.4	528.7			12628.0		1182.2	
1046+71.00 TO 1046+85.00	14.0	44	68	6.8	0.1	5.7	2.9			68.4		17.8	
1046+85.00 TO 1047+52.00	67.0	44 - 51	342	34.2	0.7	28.8	14.4			353.6		45.8	
1047+52.00 TO 1048+96.00	144.0	51	816	81.6	1.6	68.5	34.3			816.0		39.6	
1048+96.00 TO 1050+47.00	151.0	48	805	80.5	1.6	67.6	33.8			805.3			
1050+47.00 TO 1058+56.00	809.0	54	4854	485.4	9.7	407.7	203.9			4854.0		214.2	
1058+56.00 TO 1059+85.00	129.0	44	631	63.1	1.3	53.0	26.5			630.7			66.0
TOTALS				5016	101	4213	2107	560	13235	36976	766	3210	288

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	SHORT TERM PAVEMENT MARKING	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	TEMPORARY PAVEMENT MARKING - LINE 24"	WHITE	YELLOW	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	RAISED REFLECTIVE PAVEMENT MARKER
	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	SQ FT	SQ FT	EACH
906+45.00 to 941+39.00	3494	1397.6	10637.2	10637.2	0.0	0.0	0.0	0.0	0.0	0.0	13976	8696	0.0	0.0	43.7
965+32.00 to 974+28.02	896	358.4	2758.0	2758.0	0.0	0.0	0.0	0.0	0.0	0.0	3584	2290	0.0	0.0	9.5
974+28.02 to 978+22.00	393.98	118.4	1169.0	1169.0	0.0	0.0	57.0	57.0	0.0	0.0	0	2570	0.0	0.0	17.8
978+22.00 to 986+56.00	834	565.6	1792.0	1792.0	101.0	101.0	0.0	0.0	0.0	0.0	242	4109	124.8	124.8	40.4
986+56.00 to 1000+31.00	1375	992.0	3125.0	3125.0	100.0	100.0	0.0	0.0	0.0	0.0	240	7202	187.2	187.2	67.0
1000+31.00 to 1013+18.00	1287	860.4	2738.0	2738.0	203.0	203.0	0.0	0.0	30.0	30.0	547	6255	156.0	156.0	64.0
1013+18.00 to 1016+62.00	344	251.6	624.0	624.0	254.0	254.0	0.0	0.0	44.0	44.0	698	1398	78.0	78.0	21.0
1016+62.00 to 1020+33.00	371	240.8	602.5	602.5	0.0	0.0	0.0	0.0	0.0	0.0	0	1446	93.6	93.6	15.1
1020+33.00 to 1023+25.00	292	185.6	580.0	580.0	0.0	0.0	0.0	0.0	0.0	0.0	0	1346	78.0	78.0	11.6
1023+25.00 to 1027+28.00	403	266.4	832.5	832.5	0.0	0.0	0.0	0.0	0.0	0.0	0	1931	109.2	109.2	16.6
1027+28.00 to 1031+20.00	392	256.8	802.5	802.5	0.0	0.0	0.0	0.0	0.0	0.0	0	1862	109.2	109.2	16.1
1031+20.00 to 1034+56.00	336	204.8	640.0	640.0	0.0	0.0	0.0	0.0	0.0	0.0	0	1485	93.6	93.6	12.8
1034+56.00 to 1037+43.00	287	184.0	575.0	575.0	0.0	0.0	0.0	0.0	0.0	0.0	0	1334	93.6	93.6	11.6
1037+43.00 to 1040+58.00	315	194.4	607.5	607.5	0.0	0.0	0.0	0.0	0.0	0.0	0	1409	62.4	62.4	12.2
1040+58.00 to 1044+50.00	392	200.0	625.0	625.0	0.0	0.0	0.0	0.0	0.0	0.0	0	1450	93.6	93.6	12.5
1044+50.00 to 1051+05.00	655	444.4	1748.5	1748.5	533.0	533.0	0.0	0.0	32.0	32.0	1958	3113	140.4	140.4	32.8
1051+05.00 to 1055+61.00	456	286.0	815.0	815.0	804.0	804.0	0.0	0.0	63.0	63.0	2004	1646	109.2	109.2	27.2
1055+61.00 to 1058+61.00	300	157.6	860.0	860.0	515.0	515.0	47.0	47.0	32.0	32.0	1324	1741	46.8	46.8	25.0
1058+61.00 to 1059+85.00	124	80.0	448.0	448.0	179.0	179.0	0.0	0.0	0.0	0.0	815	519	31.2	31.2	1.0
TOTALS		7245	31980	31980	2689	2689	104	104	201	201	25389	51803	1607	1607	458

SURVEY MARKER SCHEDULE

LOCATION	STATION	OFFSET	DESCRIPTION	PERMANENT SURVEY MARKERS	FURNISHING AND INSTALLING PROPERTY MARKERS
				EACH	EACH
	908+50	0.6' RT	DISK IN VAULT @ NW CORNER SECTION 14 11N-3E		1
	*934+11	3.1' RT	PK NAIL @ N1/4 CORNER SECTION 14 11N-3E		1
	*959+63	0.45' RT	DISK IN VAULT @ NE CORNER SECTION 14 11N-3E		1
	*959+33.56	1.2' RT	P.I. (IRON PIN)	1	
	TOTAL			1	3

*THESE LOCATIONS FALL WITHIN PAVING OMISSION.