

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ACHSEP	ACM	ACHSEP	ACHSEP				
				1000-1A	1000-1A	Y031-1F	Y031-1F	TRAFFIC SIGNALS	TRAFFIC SIGNALS		
				ROADWAY	ROADWAY						
				HSIP	RT TURN LANE	1-255					
					STP	RAMPS 3 & 4					
				90% FEDERAL 10% STATE	80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	2% Collinsville 90% FEDERAL 5% STATE			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1							
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	40	20						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	749	631	118						
70300210	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	156	109	47						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11054	10465	589						
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	311	197	114						
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	633	571	62						
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	177	159	18						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5002	4586	416						
72000100	SIGN PANEL - TYPE 1	SQ FT	29	8	6			15			
72000200	SIGN PANEL - TYPE 2	SQ FT	49					49			
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	344	200	144						
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	344	200	144						
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	3692	2448	1244						
73000100	WOOD SIGN SUPPORT	FOOT	54	36	18						
73400100	CONCRETE FOUNDATIONS	CU YD	7.4	4.9	2.5						
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156	109	47						
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11054	10465	589						
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	311	197	114						
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	390	320	62						
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	177	159	18						
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	243	243							
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	103	87	16						
78200300	PRISMATIC CURB REFLECTOR	EACH	52	52							
80300100	LOCATING UNDERGROUND CABLE	FOOT	80			40	40				
80500100	SERVICE INSTALLATION, TYPE A	EACH	1					1			
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	213			65	148				
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	590				590				
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	109				109				
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	55				55				
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	63			16	47				
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	198				198				

*SPECIALTY ITEMS

FILE NAME =	USER NAME = conoverpj	DESIGNED -	REVISED -
ci:\projects\ed09707\plan\pin09707a.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/18/2008	DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 5 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9111	73-151S	MADISON	64	38
CONTRACT NO. 76B22			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	

Rev.