

**PAVEMENT MARKING SCHEDULE**

STATION	STATION	DESCRIPTION	SHORT-TERM PAVT MKNG (FOOT)	TEMP PVT MK LN 4" (FOOT)	TEMP PVT MK LN 8" (FOOT)	TEMP PVT MK LN 12" (FOOT)	TEMP PVT MK LN 24" (FOOT)	TEMP PAVT MK L&S (SQ FT)	WORK ZONE PAVT MK REM (SQ FT)	THPL PVT MK LTR & SYM (SQ FT)	THPL PVT MK LN 4" (FOOT)	THPL PVT MK LN 8" (FOOT)	THPL PVT MK LN 12" (FOOT)	THPL PVT MK LN 24" (FOOT)	RAISED REFL PAVT MKR (NOTE 2) (EACH)	PRISMATIC CURB REFL (EACH)	PT PVT MK- RAISED MED (SQ FT)	PAINT PVT MARK CURB (FOOT)
<b>RAMP 4</b>																		
LT 0+40	LT 0+46	Med Ramp Nose															27	35
LT 0+46	LT 0+78	CC&G												144				
LT 0+40	LT 1+78	LT EOP		144										144				
RT 0+49	RT 1+78	RT EOP		162										162				
RT 0+51	RT 0+63	Stop Bar					18		36					18				
<b>FAU RTE. 9111 (HORSESHOE LAKE ROAD)</b>																		
LT 225+48	LT 225+81	Island			114	62			138				114	62				
LT 225+32	LT 225+38	Med Ramp Nose															28	
LT 225+38	LT 225+86	EB Med Curb													3			49
LT 225+38	LT 231+67	WB CC&G		629					208		629				17			
LT 230+95	LT 231+67	WB Med Curb															24	48
LT 231+67	LT 231+73	Med Ramp Nose																
LT 226+12	LT 231+72	WB EOP							185		580							
LT 225+82	LT 231+72	WB Ln Line	118	589					194		589				16			
LT 225+57	LT 225+57	WB Stop Bar					14		28					14				
LT 228+55	LT 228+63	WB Arrows						15.6	16	15.6								
LT 228+85	LT 228+93	WB Arrow						15.6	16	15.6								
LT 225+38	LT 231+67	EB CC&G		629					208		629					32		
LT 225+86	LT 228+26	EB Lt. Turn Ln		62					20		62							
LT 228+26	LT 232+11	EB Lt. Turn Ln	77	385					127		385				11			
LT 228+97	LT 229+05	EB Arrow						15.6	16	15.6								
LT 231+12	LT 231+20	EB Arrow						15.6	16	15.6								
LT 231+15	LT 231+23	WB Arrow						15.6	16	15.6								
RT 231+67	RT 231+67	EB Stop Bar					12		24					12				
RT 225+07	RT 231+66	EB EOP		659					217		659							
RT 225+86	RT 228+25	EB Rt. Turn Ln		62					20		62							
RT 228+25	RT 231+98	EB Rt. Turn Ln	75	373					123		373				10			
RT 232+11	LT 232+11	EB Stop Bar					14		28					14				
RT 228+97	RT 229+05	EB Arrow						15.6	16	15.6								
RT 231+12	RT 231+20	EB Arrows						15.6	16	15.6								
RT 231+98	RT 232+28	Island		109	39				112			109	39					
<b>FOURNIE LANE</b>																		
LT 10+54	LT 10+73	LT EOP		52					17		52							
LT 10+65	LT 10+72	Stop Bar					24		48					24				
RT 10+22	RT 10+73	RT EOP		99					33		99							
<b>EASTPORT PLAZA DRIVE</b>																		
RT 47+83	RT 48+64	RT EOP		110					36		110							
RT 47+90	RT 48+02	Stop Bar					18		36					18				
RT 48+16	RT 48+65	Dbl Ln Line	5	48					16		48				3			
RT 48+50	LT 48+58	Lt Turn Arrow						15.6	16	15.6								
RT 48+64	LT 48+81	Bike Path			243				243									
LT 47+93	LT 47+93	Stop Bar					12		24					12				
LT 47+93	LT 48+66	Lane Line	15	73					24		73							
LT 47+92	LT 48+67	LT EOP		166					55		166							
LT 47+93	LT 48+07	Stop Bar					18		36					18				
LT 48+18	LT 48+18	Stop Bar					12		24					12				
RT 48+78	RT 49+04	RT EOP		26					9		26							
RT 48+79	RT 49+04	Dbl Ln Line	3	25					8		25				3			
LT 48+80	LT 49+04	Lane Line	5	24					8		24							
LT 48+81	LT 49+04	LT EOP		24					8		24							
<b>FAU RTE. 9111 (HORSESHOE LAKE ROAD)</b>																		
RT 232+64	RT 232+91	Island			88	34			93		901	88	34					
RT 233+84	RT 242+85	RT EOP		901					297		901							
LT 232+95	LT 242+85	Median	396	3960		255			1562		3960		255		52			
LT 233+04	LT 233+04	Stop Bar					12		24									
LT 232+71	LT 232+78	WB Stop Bar					23		46					23				
LT 232+71	LT 235+45	WB Ln Line	55	274					90		274							
LT 233+50	LT 233+58	WB Arrows						15.6	16	15.6								
LT 234+90	LT 234+98	WB Arrow						15.6	16	15.6								
LT 235+45	LT 237+25	WB Ln Line		47					16		47							
LT 233+14	LT 242+85	LT EOP		971					320		971							
<b>TOTAL</b>			<b>749</b>	<b>11054</b>	<b>311</b>	<b>633</b>	<b>177</b>	<b>156</b>	<b>5002</b>	<b>156</b>	<b>11054</b>	<b>311</b>	<b>177</b>	<b>103</b>	<b>52</b>	<b>79</b>	<b>132</b>	

**PAVEMENT MARKING NOTES:**

- RAISED REFLECTIVE PAVEMENT MARKER QUANTITY INCLUDES THE FOLLOWING TYPES:
 

64 EACH	EACH
45 EACH	EACH
EACH	EACH
109 EACH	EACH

- ONE-WAY AMBER MARKERS  
 ONE-WAY CRYSTAL MARKERS  
 TWO-WAY AMBER MARKERS  
 TOTAL

390

\*TO BE PAID FOR AS  
 PAINT PAVEMENT MARKING - LINE 12"  
 (70001150)

**EROSION CONTROL SCHEDULE**

STATION	STATION	EROSION CONTROL BLANKET (SQ YD)	TEMP EROS CONTR SEED (POUND)	TEMPORARY DITCH CHECKS (EACH)	PERIMETER EROS BAR (FOOT)	INLET & PIPE PROTECTION (EACH)
<b>RAMP 4</b>						
RT 1+56						1
LT 0+73	LT 1+78				105	
<b>HORSESHOE LAKE ROAD</b>						
LT 226+40						1
LT 226+50			1			
RT 226+50			1			
LT 226+65						1
LT 226+90						1
LT 227+15						1
LT 227+40						1
LT 227+65						1
LT 227+90						1
LT 228+15						1
LT 228+40						1
LT 228+65						1
LT 228+90						1
LT 229+15						1
LT 229+40						1
LT 229+65						1
LT 229+90						1
LT 230+00						1
LT 230+80						1
LT 231+50				1		
LT 232+92						1
RT 233+02						1
LT 233+50				1		
RT 238+00				1		
RT 239+66						1
LT 239+66						1
RT 1+78 (RAMP 4)	LT 232+17				741	
LT 225+06.5	LT 232+45					
RT 225+06.5	RT 232+12	1566	60			
RT 225+06.5	RT 232+80		20			
RT 225+38	RT 231+87				657	
LT 232+45	LT 242+85		20			
LT 232+71	LT 242+90				1031	
RT 232+80	RT 242+85		20			
RT 233+01	RT 242+90				993	
<b>EASTPORT PLAZA DRIVE</b>						
RT 48+03	RT 48+63					68
LT 48+09	LT 48+67					65
RT 48+81	RT 49+09					28
LT 48+85	LT 49+07					22
<b>TOTALS</b>		<b>1566</b>	<b>120</b>	<b>5</b>	<b>3710</b>	<b>22</b>

**PIPE UNDERDRAIN SCHEDULE**

STATION	STATION	CONC HDWL FOR P DRAIN (EACH)	PIPE UNDERDRAINS 4 (FOOT)	PIPE UNDERDRAINS 4 SP (FOOT)
<b>FAU RTE. 9111 (HORSESHOE LAKE ROAD)</b>				
LT 226+14	LT 228+90	1	276	20
LT 228+90	LT 231+70	1	280	20
LT 233+20	LT 236+57	1	336	11
LT 236+60	LT 239+80	1	300	9
LT 239+72	LT 242+85	1	313	9
RT 225+06.5	RT 228+38	1	333	10
RT 228+42	RT 231+64	1	322	14
RT 233+32	RT 236+60	1	333	23
RT 236+64	RT 239+80	1	296	4
RT 239+72	RT 242+85	1	313	4
<b>Ramp 4</b>				
LT 0+82	LT 1+54		6	