


ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.P. 885	107BR-1 111BR-1	JOHNSON	94	4
FED. ROAD DIST. NO.		ILLINOIS CONTRACT NO. 78030		

SUMMARY OF QUANTITIES

CODE #	ITEM	UNIT	TOTAL QUANTITY	HBP FUNDING 80% FEDERAL 20% STATE SN 044-0014 X080-2A	HBP FUNDING 80% FEDERAL 20% STATE SN 044-0022 X080-2A
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1025	637.5	387.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1025	637.5	387.5
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	4751	3127	1624
* 78200405	GUARDRAIL MARKERS	EACH	10	2	8
* 78200500	BARRIER WALL MARKERS	EACH	44	27	17
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	2	2
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1352	879	473
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	24	14	10
86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	2	1	1
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS	SQ FT	299	0	299
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	45	34	11
X0325864	BRIDGE APPROACH PAVEMENT REMOVAL	SQ YD	20	0	20
X0597100	CLEANING AND PAINTING EXISTING STRUCTURES	L SUM	1	1	0
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	292	0	292
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	100	44	56
Z0016000	DECK SLAB REPAIR (FULL DEPTH)	SQ YD	1	1	0
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	100	100	0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2

* SPECIALITY ITEM

 HAMPTON, LENZINI & RENWICK, INC. CIVIL & STRUCTURAL ENGINEERS LAND SURVEYORS 3086 STEVENSON DRIVE, SUITE 201 SPRINGFIELD, ILLINOIS 62703 (217) 546-3400	SUMMARY OF QUANTITIES IL. ROUTE 146 F.A.P. ROUTE 885 / SECTION 107BR-1 & 111BR-1 JOHNSON COUNTY STATION 727+23 & STATION 513+00 STRUCTURE NO. 044-0014 & 044-0022	
	ELGIN • SPRINGFIELD PROJECT NUMBER: 12-52-0007-1 DATE: 04/21/08 DESIGNED: L.P.S. CHECKED: S.W.M. DRAWN: D.T.M.	