

ROUTE NO. F.A.P. 885	SECTION 111BR-1	COUNTY JOHNSON	TOTAL SHEETS 94	SHEET NO. 8
FED. ROAD DIST. NO.		ILLINOIS	CONTRACT NO. 78030	

MAINTENANCE OF TRAFFIC							
LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	BARRIER WALL MARKERS	TEMPORARY BRIDGE TRAFFIC SIGNALS	TEMPORARY RUMBLE STRIPS	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH
STAGE I							
509+42.25 TO 516+63.75				1	6	2	
511+06.25 TO 514+93.75	387.5		17				
STAGE II							
509+42.25 TO 516+63.75							2
511+06.25 TO 514+93.75		387.5					
TOTAL	387.5	387.5	17	1	6	2	2

PAVEMENT MARKING SCHEDULE									
LOCATION	TEMPORARY			EPOXY PAVEMENT MARKING PERMANENT		SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	24" SINGLE WHITE STOP BAR	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE				
	FOOT	FOOT	FOOT	FOOT	FOOT				
FAP 885 IL RTE 146									
STAGE I									
LT. STA. 509+42.25 TO LT. STA. 516+63.75								241	
RT. STA. 509+42.25 TO RT. STA. 512+46.25								103	
RT. STA. 513+53.75 TO RT. STA. 516+63.75								103	
CL. STA. 509+42.25 TO CL. STA. 516+63.75								26	10
LT. STA. 509+42.25 TO LT. STA. 516+63.75	12	722					238		
RT. STA. 509+42.25 TO LT. STA. 511+56.25		214					71		
LT. STA. 511+56.25 TO LT. STA. 514+43.75		288					95		
LT. STA. 514+43.75 TO LT. STA. 516+63.75	12	220					73		
STAGE II									
RT. STA. 509+42.25							24		
RT. STA. 509+42.25 TO RT. STA. 516+63.75		722					238		
LT. STA. 509+42.25 TO RT. STA. 511+56.25		214					71		
RT. STA. 511+56.25 TO RT. STA. 514+43.25		287					95		
RT. STA. 514+43.25 TO LT. STA. 516+63.75		221					73		
LT. STA. 516+63.75							24		
LT STA. 509+42.25 TO LT. STA. 516+63.75		722		722					
RT STA. 509+42.25 TO RT STA. 516+63.75		722		722					
CL STA. 509+42.25 TO CL STA. 516+63.75			180		180	4			
SUBTOTAL	24	4332	180	1444	180	4	1002	473	10
TOTAL	24	4512		1624		4	1002	473	10

GUARDRAIL						
	GUARDRAIL REMOVAL	* VERTICAL ADJUSTMENT OF GUARDRAIL	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 6A	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKERS
	FOOT	FOOT	EACH	EACH	EACH	EACH
STAGE I						
RT. STA. 512+02.39 TO RT. STA. 512+46.39	44					
RT. STA. 512+02.39 TO RT. STA. 512+46.39				1		
RT. STA. 511+77.39 TO RT. STA. 512+02.39		25				
RT. STA. 513+53.71 TO RT. STA. 513+93.39	40					
RT. STA. 513+53.71 TO RT. STA. 514+47.61			1	1	1	
RT. STA. 512+02.39 TO RT. STA. 514+47.61						4
LT. STA. 512+06.83 TO LT. STA. 512+46.29	40					
LT. STA. 511+52.39 TO LT. STA. 512+46.39			1	1	1	
STAGE II						
LT. STA. 513+53.71 TO LT. STA. 513+97.61	44					
LT. STA. 513+53.71 TO LT. STA. 513+97.61				1		
LT. STA. 513+97.61 TO LT. STA. 514+22.61		25				
LT. STA. 511+52.39 TO LT. STA. 513+97.61						4
TOTAL	168	50	2	4	2	8

* COST OF VERTICAL ADJUSTMENT OF GUARDRAIL IS INCLUDED IN TRAFFIC BARRIER TERMINAL TYPE 6A

HAMPTON, LENZINI & RENWICK, INC.
 CIVIL & STRUCTURAL ENGINEERS
 LAND SURVEYORS

3085 STEVENSON DRIVE, SUITE 201
 SPRINGFIELD, ILLINOIS 62703
 (217) 546-3400

HLR

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-52-0007-1 DATE: 04/21/08
 DESIGNED: L.F.S. CHECKED: S.W.M. DRAWN: D.T.M.

SCHEDULE OF QUANTITIES

IL. ROUTE 146 OVER BELL POND
 F.A.P. ROUTE 885 / SECTION 111BR-1
 JOHNSON COUNTY
 STATION 513+00
 STRUCTURE NO. 044-0022