

PAVEMENT MARKING SCHEDULE				
LOCATION	DESCRIPTION	SHORT-TERM PAVEMENT MARKING	PAINT PAVEMENT MARKING - LINE	TEMP PAVEMENT MARKING - LINE
			4"	4"
		FOOT	FOOT	FOOT
STA 816+22 TO STA 819+73 LT	SOLID WHITE EDGE LINE			351
STA 814+63.5 TO STA 820+87.5 RT	SOLID WHITE EDGE LINE			624
STA 816+22 TO STA 819+73 RT	SOLID WHITE EDGE LINE			351
STA 815+00.5 TO STA 821+38.5 LT	SOLID WHITE EDGE LINE			638
STA 814+40.5 TO STA 821+48.5	SKIP DASH YELLOW CENTERLINE	71		
STA 814+40.5 TO STA 821+48.5	SKIP DASH YELLOW CENTERLINE			177
STA 816+50 TO STA 821+48.5	SOLID YELLOW CENTERLINE			499
STA 816+22 TO STA 819+73 LT	SOLID WHITE EDGE LINE		351	
STA 816+22 TO STA 819+73 RT	SOLID WHITE EDGE LINE		351	
STA 814+40.5 TO STA 821+48.5	SKIP DASH YELLOW CENTERLINE		177	
STA 816+50 TO STA 821+48.5	SOLID YELLOW CENTERLINE		499	
TOTALS		71	1378	2640

GUARDRAIL SCHEDULE						
LOCATION	TRAFFIC BARRIER TERMINAL TYPE 6A	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	STEEL RAILING, TYPE SM	
	EACH	EACH	EACH	EACH	FOOT	
NE QUADRANT	1		1			
NW QUADRANT	1	1	1			
SE QUADRANT	1	1	1			
SW QUADRANT	1		1			
BRIDGE				4	167	
TOTALS		4	2	4	4	167

GUARDRAIL REMOVAL SCHEDULE	
LOCATION	FOOT
NE QUADRANT	45*
NW QUADRANT	45*
SE QUADRANT	45*
SW QUADRANT	45*
TOTALS	180*

BASE COURSE SCHEDULE			
LOCATION	PCC BASE COURSE, 10"	BASE COURSE WIDENING, 10"	
	SQ YD	SQ YD	
NE QUADRANT	5	51	
NW QUADRANT	5	55	
SE QUADRANT	5	51	
SW QUADRANT	5	55	
TOTALS	20	212	

PAVEMENT MARKER SCHEDULE	
LOCATION	RRPM REMOVAL
	EACH
STA 817+80	1
STA 818+60	1
TOTALS	2

EROSION CONTROL SCHEDULE		
LOCATION	PERIMETER EROSION BARRIER	TEMPORARY EROSION CONTROL SEEDING (2 APPLICATIONS)
	FOOT	POUND
NE QUADRANT	185	4
NW QUADRANT	195	4
SE QUADRANT	185	4
SW QUADRANT	195	4
TOTALS	760	16

* QUANTITY MAY VARY DEPENDING ON LAYOUT PROPOSED BY THE CONTRACTOR. SEE MISCELLANEOUS DETAILS SHEET FOR DETAILS.

WORK ZONE AND PAVEMENT MARKING REMOVAL SCHEDULE			
LOCATION	PAVEMENT MARKING DESCRIPTION	WORK ZONE PAVEMENT REMOVAL	PAVEMENT MARKING REMOVAL
		SQ FT	SQ FT
STA 814+40.5 TO STA 816+05	CENTER LINE		14
STA 819+90 TO STA 821+48.5	CENTER LINE		13
STA 816+22 TO STA 819+73 LT	EDGE LINE		117
PHASE 1 EDGE LINES	TEMPORARY	325	
STA 816+22 TO STA 817+47 RT	EDGE LINE		41
STA 818+60 TO STA 819+73 RT	EDGE LINE		38
PHASE 2 EDGE LINES	TEMPORARY	330	
CENTER LINE	SHORT-TERM	24	
CENTER LINE	TEMPORARY	225	
TOTALS		904	223

SEEDING SCHEDULE							
LOCATION	SEEDING CLASS 2A	SEEDING CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2
	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
NE QUADRANT	0.02	0.02	1.8	1.8	1.8	0.04	0.04
NW QUADRANT	0.02	0.02	1.8	1.8	1.8	0.04	0.04
SE QUADRANT	0.02	0.02	1.8	1.8	1.8	0.04	0.04
SW QUADRANT	0.02	0.02	1.8	1.8	1.8	0.04	0.04
TOTALS	0.08	0.08	7.2	7.2	7.2	0.16	0.16

HMA SURF REMOVAL SCHEDULE		
LOCATION	BUTT JOINT	2"
	SQ YD	SQ YD
STA 817+74	86	
STA 818+60	87	
WEST ABUTMENT		5
EAST ABUTMENT		5
TOTALS	173	10

NOTE: HMA SURFACE REMOVAL (2") IS INCLUDED IN THE COST OF REMOVAL OF EXISTING SUPERSTRUCTURE.

REMOVAL SCHEDULE	
LOCATION	PAVEMENT REMOVAL SQ YD
NE QUADRANT	5
NW QUADRANT	5
SE QUADRANT	5
SW QUADRANT	5
TOTALS	20

EARTHWORK SCHEDULE				
LOCATION	SUITABLE EARTH EXCAVATION (WIDENING)	SUITABLE EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT (NOT A PAY ITEM)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
NE QUADRANT	12	9	1	+8
NW QUADRANT	14	11	1	+10
SE QUADRANT	13	10	1	+9
SW QUADRANT	13	10	2	+8
TOTALS	52	40	5	+35

NOTE:
1. EXCAVATION USED AS EMBANKMENT = (SUITABLE EARTH EXCAVATION + SUITABLE INCIDENTAL EXCAVATION) x 0.75

PAVING SCHEDULE			
LOCATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SURFACE COURSE, MIX C, N90
	GALLON	TON	TON
WEST APPROACH	45	0.3	9.8
EAST APPROACH	43	0.3	9.8
TOTALS	88	0.6	19.6



FILE NAME =	USER NAME = #USER#	DESIGNED - JAH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAP ROUTE 885 (IL 146) SCHEDULE OF QUANTITIES	F.A.P. RTE. 885	SECTION 111BR-2	COUNTY POPE	TOTAL SHEETS 69	SHEET NO. 42		
#FILES#	PLOT SCALE = #SCALE#	CHECKED - JAH	REVISED -			SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 78033		
	PLOT DATE = #DATE#	DATE -	REVISED -			FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT						