

SUMMARY OF QUANTITIES

Construction Code: *SFTY-1B*

Item #	Items	Unit	Chicago St. Quantity	City Park Quantity	Total
20200100	Earth Excavation	C.Y.	12.8	0	12.8
20400800	Furnished Excavation	C.Y.	100	0	100
40800050	Incidental Hot Mix Asphalt Surfacing	Ton	4.4	0	4.4
42300200	Portland Cement Concrete Driveway Pavement, 6 Inch	S.Y.	188.3	0	188.3
42400100	Portland Cement Concrete Sidewalk, 4 Inch	S.F.	9,510.7	0	9,510.7
42400800	Detectable Warnings	S.F.	346	0	346
44000200	Driveway Pavement Removal	S.Y.	229.3	0	229.3
550A0410	Storm Sewers, Class A, Type 2 24"	FT.	8	0	8
*56109210	Water Valves to be Adjusted	EA.	2	0	2
60255500	Manholes to be Adjusted	EA.	1	0	1
67100100	Mobilization	L.S.	1	1	2
*70103700	Traffic Control Complete	L.S.	1	0	1
*81400115	Handhole to be Adjusted	EA.	1	0	1
*Z0013798	Construction Layout	L.S.	1	1	2
*XX003952	Temporary Erosion Control (Complete)	L.S.	1	1	2
*XX006344	Sodding (Complete)	S.Y.	1,415.5	334.7	1,750.2
*X0300380	Portland Cement Concrete Sidewalk, 5 Inch Exposed Aggregate	S.F.	0	6,622.3	6,622.3
X0324057	Wooden Fence Relocation	FT.	50	0	50
*X4400220	Curb Removal and Replacement	FT.	221.5	0	221.5

Δ Specialty Items

**SCHEDULE OF QUANTITIES
CHICAGO STREET**

20200100	EARTH EXCAVATION RT., STA. 38+86.57-STA. 39+23.52	C.Y.	12.8		
	TOTAL		12.8		
20400800	FURNISHED EXCAVATION	C.Y.	100		
	TOTAL		100		
40800050	INCIDENTAL HOT MIX ASPHALT SURFACING STA. 6+64	TON	4.4		
	TOTAL		4.4		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6" STA. 4+18 STA. 6+64 STA. 7+91 STA. 14+38 STA. 18+95	S.Y.	41.0 9.5 74.1 26.8 36.9		
	TOTAL		188.3		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH STA. 1+21.44-STA. 4+07.53 STA. 4+29.40-STA. 5+41.11 STA. 5+81.62-STA. 6+53.47 STA. 6+72.87-STA. 7+67.49 STA. 8+14.54-STA. 10+05.62 STA. 10+45.03-STA. 12+54.03 STA. 12+92.67-STA. 14+30.34 STA. 14+45.77-STA. 15+03.04 STA. 15+41.19-STA. 17+75.99 STA. 18+10.02-STA. 18+80.34 STA. 19+08.07-STA. 20+80.77 STA. 21+14.38-STA. 22+09.34 STA. 22+18.72-STA. 23+06.52 STA. 33+19.29-STA. 37+94.56 STA. 38+84.89-STA. 39+21.94 STA. 39+76.95-STA. 40+22.42	S.F.	1144.4 446.8 287.4 378.5 764.3 836.0 550.7 229.1 939.2 281.3 690.8 379.8 351.2 1901.1 148.2 181.9		
	TOTAL		9,510.7		

**SCHEDULE OF QUANTITIES
CHICAGO STREET (CONT.)**

42400800	DETECTABLE WARNINGS STA. 1+23.98 STA. 5+38.51 STA. 5+82.31 STA. 10+03.67 STA. 10+46.89 STA. 12+52.07 STA. 12+94.59 STA. 15+01.07 STA. 15+43.09 STA. 17+73.96 STA. 18+12.02 STA. 20+78.73 STA. 21+16.21 STA. 37+94.56 STA. 38+84.89 STA. 39+21.92 STA. 39+76.97	S.F.	23.8 26.5 17.8 17.9 24.0 25.0 24.3 17.1 23.8 30.3 26.6 29.0 19.9 8.1 12.1 11.7 8.1		
	TOTAL		346		
44000200	DRIVEWAY PAVEMENT REMOVAL STA. 4+18 STA. 6+64 STA. 7+91 STA. 14+38 STA. 18+95	S.Y.	41.0 35.6 89.0 26.8 36.9		
	TOTAL		229.3		
550A0410	STORM SEWERS, CLASS A, TYPE 2 24" 22.63' RT. STA. 37+75.97	FT.	8		
	TOTAL		8		
56109210	WATER VALVES TO BE ADJUSTED 1.84' RT. STA. 8+54.51 2.25' LT. STA. 9+54.07	EACH	1 1		
	TOTAL		2		
60255500	MANHOLES TO BE ADJUSTED .55' RT., STA. 5+22.57	EACH	1		
	TOTAL		1		
67100100	MOBILIZATION	L.S.	1		
	TOTAL		1		
70103700	TRAFFIC CONTROL COMPLETE	LS	1		
	TOTAL		1		
81400115	HANDHOLE TO BE ADJUSTED 20.61' RT. STA. 39+23.77	EACH	1		
	TOTAL		1		
Z0013798	CONSTRUCTION LAYOUT	L.S.	1		
	TOTAL		1		
XX003952	TEMPORARY EROSION CONTROL (COMPLETE)	L.S.	1		
	TOTAL		1		

**SCHEDULE OF QUANTITIES
CHICAGO STREET (CONT.)**


XX006344	SODDING (COMPLETE)	S.Y.	37.2 5.6 61.3 49.6 31.9 42.1 84.9 92.9 61.2 25.5 26.1 31.3 34.9 33.9 42.2 39.0 121.3 410.4 164.0 20.2		
	TOTAL		1,415.5		
X0324057	WOODEN FENCE RELOCATION 0.96' RT. STA. 16+69.24-0.85' RT. STA. 17+19.43	FT.	50		
	TOTAL		50		
X4400220	CURB REMOVAL AND REPLACEMENT STA. 1+23.98 STA. 5+38.51 STA. 5+82.31 STA. 10+03.67 STA. 10+46.89 STA. 12+52.07 STA. 12+94.59 STA. 15+01.07 STA. 15+43.09 STA. 17+73.96 STA. 18+12.02 STA. 20+78.73 STA. 21+16.21 STA. 37+94.56 STA. 38+84.89 STA. 39+21.92 STA. 39+76.97	F.T.	15.9 17.4 13.0 11.9 15.4 16.5 16.2 11.6 16.0 19.4 17.4 18.6 13.1 4.0 5.2 5.9 4.0		
	TOTAL		221.5		

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION CUBIC YARD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE CUBIC YARD	EMBANKMENT CUBIC YARD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CUBIC YARD
STA. 35+47.73 TO STA. 37+91.79	0	0	109.6	-109.6
STA. 38+86.57 TO STA. 39+23.52	12.8	9.6	0	9.6
TOTAL	12.8	9.6	109.6	-100.0

EARTH EXCAVATION=12.8 CUBIC YARDS
FURNISHED EXCAVATION=100.0 CUBIC YARDS

REVISIONS	DATE	DESCRIPTION
1	8-6-07	IDOT REVIEW
2	9-10-07	IDOT REVIEW
3	9-28-07	IDOT REVIEW
4	11-14-07	IDOT FINAL REVIEW
5	12-17-07	GENESECO ADDITION
6	01-16-08	



**SOUTH CHICAGO ST/CITY PARK SIDEWALK
GENESECO, ILLINOIS**

SUMMARY & SCHEDULE OF QUANTITIES

Missman Project No:
A07-L019

File Name:
SUMSCHED.dwg

© COPYRIGHT 2007
ALL RIGHTS RESERVED

Drawn By: SJD

Checked By: BJV

Date: AUG 2007