

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.S. 321	05-00205-02-RS	IROQUOIS	76	5
FED. ROAD DIST. NO.		ILLINOIS	CONTRACT NO. 67363	

ENTRANCE AND SIDEROAD SCHEDULE													
LOCATION	TYPE	EXISTING SURFACE TYPE	EXISTING WIDTH	PROPOSED SURFACE TYPE	PROPOSED WIDTH	TYPE	RADIUS	SHOULDER WIDTH	INCIDENTAL HMA SURFACING	AGGREGATE SURFACE COURSE TY B	BIT. MATL. PRIME COAT	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE REMOVAL BUTT-JOINT
			FEET		FEET		FEET	FEET	TON	TON	GAL.	SQ. YD.	SQ. YD.
CH 4													
LT. STA. 35+26.00	FE	EARTH	35	AGG	35	rural	10	4		8			
RT. STA. 46+02.00	FE	EARTH	24	AGG	24	rural	10	4		6			
RT. STA. 53+92.00	PE WITH MB TURNOUT	BIT	13	HMA	16	rural	17	4	4		4	9	9
RT. STA. 56+12.00	PE WITH MB TURNOUT	AGG	12	HMA	12	rural	17	4	4		3		
RT. STA. 56+64.00	PE	AGG	8	HMA	12	rural	17	4	3		3		
RT. STA. 58+64.00	PE WITH MB TURNOUT	AGG	13	HMA	14	rural	17	4	4		4		
LT. STA. 63+31.00	FE	EARTH	28	AGG	28	rural	10	4		7			
RT. STA. 63+78.00	PE WITH MB TURNOUT	AGG	14	HMA	19	rural	17	4	5		4		
RT. STA. 65+76.00	FE	EARTH	16	AGG	16	rural	10	4		4			
RT. STA. 75+00.00	FE	AGG	16	AGG	16	rural	10	4		4			
LT. STA. 75+00.00	FE	EARTH	18	AGG	18	rural	10	4		4			
LT. STA. 78+19.00	FE	EARTH	16	AGG	16	rural	10	4		4			
LT. STA. 84+79.00	PE	BIT	18	HMA	27	rural	17	4	5		4	15	15
LT. STA. 89+41.00	FE	EARTH	16	AGG	16	rural	10	4		4			
RT. STA. 91+48.00	MB TURNOUT	BIT		HMA		rural		4	1		5		
LT. STA. 91+51.00	PE	AGG	30	HMA	28	rural	17	4	5		4		
RT. STA. 96+58.00	FE	EARTH	20	AGG	20	rural	10	4		5			
LT. STA. 103+52.00	FE	EARTH	16	AGG	16	rural	10	4		4			
RT. STA. 104+67.00	FE	AGG	20	AGG	20	rural	10	4		5			
LT. STA. 112+43.00	PE	AGG	20	HMA	21	rural	17	4	4		4		
LT. STA. 113+26.00	FE	EARTH	16	AGG	16	rural	10	4		4			
RT. STA. 117+30.00	MB TURNOUT	BIT		HMA		rural		4			5		
LT. STA. 117+36.00	PE	AGG	12	HMA	18	rural	17	4	4		3		
RT. STA. 119+75.00	FE	EARTH	18	AGG	18	rural	10	4		4			
RT. STA. 122+65.00	PE WITH MB TURNOUT	AGG	12	HMA	12	rural	17	4	4		3		
LT. STA. 128+79.00	FE	EARTH	24	AGG	24	rural	10	4		6			
RT. STA. 132+79.00	FE	EARTH	16	AGG	16	rural	10	4		4			
LT. STA. 139+35.00	FE	EARTH	20	AGG	20	rural	10	4		5			
LT. STA. 153+31.00	FE	EARTH	20	AGG	20	rural	10	4		5			
RT. STA. 155+86.00	FE	EARTH	25	AGG	25	rural	10	4		6			
RT. STA. 164+90.00	FE	EARTH	16	AGG	16	rural	10	4		4			
LT. STA. 169+53.00	PE	AGG	16	HMA	16	rural	17	4	3		3		
LT. STA. 178+14.00	FE	AGG	16	AGG	16	rural	10	4		4			
LT. STA. 183+12.00	PE WITH MB TURNOUT	AGG	12	HMA	13	rural	17	4	4		4		
RT. STA. 190+28.00	PE	AGG	28	HMA	30	rural	17	4	6		6		
TOTAL ENTRANCES									56	97	59	24	24
SIDE ROADS													
LT. STA. 32+71.88	SR 1100 E. (NORTH)	HMA	20	HMA	20	rural	50	0	27	0	17	11	22
RT. STA. 32+70.87	SR 1100 E. (SOUTH)	HMA	22	HMA	22	rural	50	0	28	0	18	12	24
LT. STA. 86+37.62	SR 1200 E. (NORTH)	HMA	22	HMA	22	rural	25	0	9	0	6	12	24
RT. STA. 86+37.62	SR 1200 E. (SOUTH)	HMA	19	HMA	19	rural	50	0	26	0	17	11	21
LT. STA. 139+79.28	SR 1300 E. (NORTH)	HMA	14	HMA	14	rural	30	0	10	0	7	8	16
RT. STA. 139+79.28	SR 1300 E. (SOUTH)	HMA	17	HMA	17	rural	40	0	18	0	11	9	19
TOTAL SIDEROADS									118	0	76	63	126
TOTAL PROJECT									174	97	135	87	150

PLOT DATE 15/16/2008 FILE NAME = 46002-ah-t-schedule2.dgn

HAMPTON, LENZINI & RENWICK, INC.
 CIVIL & STRUCTURAL ENGINEERS
 LAND SURVEYORS

HLR

3085 STEVENSON DRIVE, SUITE 201
 SPRINGFIELD, ILLINOIS 62703
 (217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 07.0120.320 DATE: 05/06/08
 DESIGNED: L.F.S. CHECKED: DRAWN: W.J.S.

SCHEDULE OF QUANTITIES

F.A.S. 321 / C.H. 4

SECTION 05-00205-02-RS

IROQUOIS COUNTY