

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9315	05-00032-02-PV	MONROE	55	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 97349				

CODE NO.	ITEM	UNIT	URBAN - MONROE CO.
			FEDERAL 75% CITY 25% J000-2A
20200100	EARTH EXCAVATION	CU. YD.	392
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU. YD.	621
20400800	FURNISHED EXCAVATION	CU. YD.	148
20900330	GRANULAR BACKFILL	TON	1,948
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU. YD.	183
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ. YD.	36
25000110	SEEDING, CLASS 1A	ACRE	0.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	70
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	70
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	70
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.5
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ. YD.	3,403
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	75
28000300	TEMPORARY DITCH CHECKS	EACH	7
28000400	PERIMETER EROSION BARRIER	FOOT	102
28000500	INLET AND PIPE PROTECTION	EACH	2
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ. YD.	77
28200200	FILTER FABRIC	SQ. YD.	77
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A, 4"	SQ. YD.	3,623
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A, 8"	SQ. YD.	159
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A, 12"	SQ. YD.	358
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ. YD.	270
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	562
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	232
40600300	AGGREGATE (PRIME COAT)	TON	3
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	110
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	48
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ. YD.	3,025
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ. YD.	92
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ. YD.	34
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ. FT.	2,699.5
42400800	DETECTABLE WARNINGS	SQ. FT.	35.5
44000100	PAVEMENT REMOVAL	SQ. YD.	257
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4
44000600	SIDEWALK REMOVAL	SQ. FT.	1,600
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1
54216003	PRECAST REINFORCED CONCRETE PIPE ELBOW 48"	EACH	1
54216180	REINFORCED CONCRETE PIPE TEE, 12" PIPE WITH 12" RISER	EACH	2
54216220	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 12" RISER	EACH	3
54216242	REINFORCED CONCRETE PIPE TEE, 48" PIPE WITH 12" RISER	EACH	5
54216960	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 18" RISER	EACH	1
54217700	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 24" RISER	EACH	1
54248515	CONCRETE COLLAR	EACH	16
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	209
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	24
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	234
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	154
550A2420	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 48"	FOOT	78
550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	19
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	38
550B0070	STORM SEWERS, CLASS B, TYPE 1 15"	FOOT	11
550B0340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT	73
550B0360	STORM SEWERS, CLASS B, TYPE 2 15"	FOOT	33
550B0380	STORM SEWERS, CLASS B, TYPE 2 18"	FOOT	63
550B0410	STORM SEWERS, CLASS B, TYPE 2 24"	FOOT	11
550B2540	STORM SEWERS, RUBBER GASKET, CLASS B, TYPE 2 18"	FOOT	23
550B2560	STORM SEWERS, RUBBER GASKET, CLASS B, TYPE 2 24"	FOOT	18

* SPECIAL PROVISION ITEMS
 ^ SPECIALTY ITEMS

CODE NO.	ITEM	UNIT	URBAN - MONROE CO.
			FEDERAL 75% CITY 25% J000-2A
55100300	STORM SEWER REMOVAL 8"	FOOT	65
55101200	STORM SEWER REMOVAL 24"	FOOT	63
55101400	STORM SEWER REMOVAL 30"	FOOT	290
55101600	STORM SEWER REMOVAL 36"	FOOT	152
60100925	PIPE DRAINS 8"	FOOT	75
60226200	RESTRICTED DEPTH MANHOLES, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1
60240385	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	1
60242500	INLETS, SPECIAL, NO. 1	EACH	5
60242600	INLETS, SPECIAL, NO. 2	EACH	1
60242700	INLETS, SPECIAL, NO. 3	EACH	6
60247200	JUNCTION BOX	EACH	2
60500060	REMOVING INLETS	EACH	3
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1,326.5
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	50
67100100	MOBILIZATION	L. SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L. SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM	1
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2,584
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	304
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	37
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	5
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	9
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	4
XX003308	TRENCH DRAIN	FOOT	32
Z0041700	PLUG EXISTING STORM SEWER	EACH	1

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE _____ DRAWN BY _____
 DATE _____ CHECKED BY _____

CADD FILE: 5981/5981 - summary.dgn
 PLOTTED: 5/23/2008

H.M. & G. NO. 5981