

STORM SEWER SCHEDULE (CONTINUED NEXT SHEET)

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9315	05-00032-02-PV	MONROE	55	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 97349				

LOCATION	STATION - STATION	GRANULAR BACKFILL TON	STORM SEWER REMOVAL				REMOVING INLETS EACH	PIPE DRAIN 8" FOOT	STORM SEWERS												REINFORCED CONCRETE PIPE TEE					CONC. COLLAR EACH	R.C. ELBOW 48" EACH	P.R.C. FLAR. END SECT. 48" EACH		
			8"	24"	30"	36"			CLASS A						CLASS B						12" W/12" RISER EACH	36" W/12" RISER EACH	36" W/18" RISER EACH	36" W/24" RISER EACH	48" W/12" RISER EACH					
									TYPE 1	TYPE 1 RUBBER GASKET	TYPE 2	TYPE 2 RUBBER GASKET	TYPE 1	TYPE 2	TYPE 2 RUBBER GASKET	12"	15"	12"	15"	18"									24"	18"
MOORE STREET (LT. & RT.)																														
ES-1 TO JB-1	RT. STA. 117+63.71 - TA. 118+50	64.0	-	-	-	-	-	-	78.2	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	1
AL-1 TO JB-1	LT. STA. 117+90 - STA. 118+50	50.7	32.0	-	-	-	-	28.0	43.5	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2	-
REMOVAL	RT. STA. 118+23 - STA. 119+72.50	81.9	-	-	-	151.5	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
JB-1 TO JB-2	RT. STA. 118+50 - STA. 120+41.15	403.5	-	-	-	-	-	-	-	-	-	-	153.5	-	-	-	-	-	-	-	-	-	-	-	-	-	-	5	5	
REMOVAL	RT. STA. 119+72.50 - STA. 122+62.30	269.6	-	-	289.6	-	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
GRAND AVE./MOORE ST. (SHOWING MOORE ST. STA.)																														
GL-1 TO GMHL-1	LT. STA. 120+23.84 - STA. 120+39	17.6	-	-	-	-	-	-	-	-	-	-	-	-	19.3	10.6	-	-	-	-	-	-	-	-	-	-	-	-	-	
GMHL-1 TO JB-2	LT. STA. 120+39 - STA. 120+41.15	69.6	-	-	-	-	-	-	-	-	-	-	-	-	-	-	32.4	-	-	-	-	-	-	-	-	-	-	-	-	
MOORE STREET (LEFT FROM GRAND AVE., NORTH)																														
GMHL-1 TO AL-4	LT. STA. 120+39 - STA. 122+17.11	107.3	32.7	-	-	-	-	46.2	164.7	-	-	-	-	-	18.4	-	-	-	-	-	-	-	-	-	-	-	-	4	-	
MOORE STREET (LT. & RT.)																														
JB-2 TO IMHR-1	RT. STA. 120+41.15 - STA. 123+09.49	592.3	-	-	-	-	-	-	-	-	-	233.5	-	-	-	12.0	-	-	-	-	-	-	-	-	3	1	1	-	5	
REMOVAL	RT. STA. 122+62.30 - STA. 123+12.63	37.9	-	50.0	-	-	2	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
IMHR-1 TO IMHR-2	RT. STA. 123+09.49 - STA. 123+34.37	36.8	-	-	-	-	-	-	-	-	-	-	18.4	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
IMHR-2 TO IL-1 & TO IR-12	A.R. STA. 123+34.37	57.3	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	32.6	-	-	-	-	-	-	-	-	-	-	
IMHR-2 TO CONCRETE PLUG	RT. STA. 123+34.37 - STA. 123+68.30	42.5	-	-	-	-	-	-	-	-	24.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
ILLINOIS AVENUE (SHOWING ILLINOIS AVE. STA.)																														
TR-9 TO BR-1	RT. STA. 21+44.30 - STA. 22+62.53	35.9	-	13.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	17.8	-	
TR-10 TO IR-1	RT. STA. 21+44.30 - STA. 22+28.66	37.4	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
IMHR-1 TO IR-2	LT. STA. 21+93.51 - STA. 22+17.55	35.5	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	20.0	-	-	-	-	-	-	-	-	-	-	
IR-2 TO IR-3	LT. STA. 22+17.55 - STA. 22+35.33	8.4	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	5.8	-	-	-	-	-	-	-	-	-	-	
IR-3 TO IR-4	LT. STA. 22+35.33 - STA. 22+47.93	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2.0	-	-	-	-	-	-	-	-	-	-	
IR-4 TO IR-5	LT. STA. 22+47.93 - STA. 22+60.54	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2.0	-	-	-	-	-	-	-	-	-	-	
IR-6 & IR-7 TO IR-3	LT. STA. 22+27.29 - STA. 22+32.71	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3.6	-	-	-	-	-	-	-	-	-	-	
IR-8 & IR-9 TO IR-4	LT. STA. 22+39.89 - STA. 22+45.31	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3.6	-	-	-	-	-	-	-	-	-	-	
IR-10 & IR-11 TO IR-5	LT. STA. 22+52.49 - STA. 22+57.91	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3.6	-	-	-	-	-	-	-	-	-	-	
TOTALS (NOT ADJUSTED FOR DEG. OF ACCURACY):		1,948.2	64.7	63.0	289.6	151.5	3	74.2	208.2	78.2	24.0	233.5	153.5	18.4	37.7	10.6	72.1	32.4	62.4	10.8	23.0	17.8	2	3	1	1	5	16	1	1
TOTALS (ADJ. FOR DEG. OF ACCURACY. PAY QTY.):		1,948	65	63	290	152	3	75	209	79	24	234	154	19	38	11	73	33	63	11	23	18	2	3	1	1	5	16	1	1

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 STORM SEWER

SCALE _____ DRAWN BY _____
 DATE _____ CHECKED BY _____

CADD FILE: 5881/5881_sch.dwg
 PLOTTED: 8/24/05

H.M. & G. NO. 5881