

STORM SEWER SCHEDULE (CONTINUED)

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9315	05-00032-02-PV	MONROE	55	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 97349				

LOCATION	STATION - STATION	INLETS					SPECIAL NO. 1	SPECIAL NO. 2	SPECIAL NO. 3	RESTRICTED DEPTH MAN-HOLE, 6' DIA. W/TY. 1 FR. & CLOSED LID	TRENCH DRAIN	JUNCTION BOX	PLUG STORM SEWER
		TYPE A		TYPE B									
		W/TY. 8 GRATE	W/TY. 3V FRAME & GRATE	W/TY. 1 FRAME & CLOSED LID	W/TY. 3V FRAME & GRATE	W/SPECIAL FRAME & GRATE							
MOORE STREET (LEFT & RIGHT)													
ES-1 TO JB-1	RT. STA. 117+63.71 - TA. 118+50	-	-	-	-	-	-	-	-	-	-	-	
AL-1 TO JB-1	LT. STA. 117+90 - STA. 118+50	-	1	-	1	-	-	-	-	-	-	-	
REMOVAL	RT. STA. 118+23 - STA. 119+72.50	-	-	-	-	-	-	-	-	-	-	-	
JB-1 TO JB-2	RT. STA. 118+50 - STA. 120+41.15	-	3	-	-	-	-	-	-	32	1	-	
REMOVAL	RT. STA. 119+31.06 - STA. 122+62.30	-	-	-	-	-	-	-	-	-	-	-	
GRAND AVE./MOORE ST. (SHOWING MOORE ST. STA.)													
GL-1 TO GMHL-1	LT. STA. 120+23.84 - STA. 120+39	-	1	-	2	-	-	-	-	-	-	-	
GMHL-1 TO JB-2	LT. STA. 120+39 - STA. 120+41.15	-	-	-	-	-	-	-	1	-	-	-	
MOORE STREET (LEFT FROM GRAND AVE., NORTH)													
GMHL-1 TO AL-2	LT. STA. 120+39 - STA. 122+17.11	2	1	1	-	-	-	-	-	-	-	-	
MOORE STREET (LEFT & RIGHT)													
JB-2 TO IMHR-1	RT. STA. 120+41.15 - STA. 123+09.49	-	3	-	-	-	-	-	-	-	1	-	
REMOVAL	RT. STA. 122+62.30 - STA. 123+12.63	-	-	-	-	-	-	-	-	-	-	-	
IMHR-1 TO IMHR-2	RT. STA. 123+09.49 - STA. 123+34.37	-	-	-	-	1	-	-	1	-	-	-	
IMHR-2 TO IL-1 AND TO IR-12	A.R. STA. 123+34.37	-	-	-	-	-	1	-	1	-	-	-	
IMHR-2 TO CONCRETE PLUG	RT. STA. 123+34.37 - STA. 123+68.30	-	-	-	-	-	-	-	-	-	-	1	
ILLINOIS AVENUE (SHOWING ILLINOIS AVE. STA.)													
TR-9 TO BR-1	RT. STA. 21+44.30 - STA. 122+62.53	-	-	-	-	-	-	-	-	-	-	-	
TR-10 TO IR-1	RT. STA. 21+44.30 - STA. 22+28.66	-	-	-	-	1	1	-	-	-	-	-	
IMHR-1 TO IR-2	LT. STA. 21+93.51 - STA. 22+17.55	-	-	-	-	-	-	-	-	-	-	-	
IR-2 TO IR-3	LT. STA. 22+17.55 - STA. 22+35.33	-	-	-	1	-	-	-	-	-	-	-	
IR-3 TO IR-4	LT. STA. 22+35.33 - STA. 22+47.93	-	-	-	-	1	-	-	-	-	-	-	
IR-4 TO IR-5	LT. STA. 22+47.93 - STA. 22+60.54	-	-	-	-	2	-	-	-	-	-	-	
IR-6 & IR-7 TO IR-3	LT. STA. 22+27.29 - STA. 22+32.71	-	-	-	-	-	-	2	-	-	-	-	
IR-8 & IR-9 TO IR-4	LT. STA. 22+39.89 - STA. 22+45.31	-	-	-	-	-	-	2	-	-	-	-	
IR-10 & IR-11 TO IR-5	LT. STA. 22+52.49 - STA. 22+57.91	-	-	-	-	-	-	2	-	-	-	-	
TOTALS (NOT ADJUSTED FOR DEGREE OF ACCURACY):		2	9	1	4	1	5	1	6	3	32	1	
TOTALS (ADJ. FOR DEG. OF ACCURACY. PAY QTY.):		2	9	1	4	1	5	1	6	3	32	1	

CADD FILE: 5881/5881-00002.dgn
 PLOTTED: 8/04/08

H.M. & G. NO. 5581

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
STORM SEWER

SCALE _____ DRAWN BY _____
 DATE _____ CHECKED BY _____