

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	0005						CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	0005					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	58	58						44000600	SIDEWALK REMOVAL	SO FT	2331	2331					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	95	95						44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	220	220					
25200110	SODDING, SALT TOLERANT	SO YD	95	95						44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	124	124					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	168	168						44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	65	65					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	4520	4520						44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	475	475					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	96	96					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1230	1230						44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	240	240					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	11146	11146						60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	6	6					
42001300	PROTECTIVE COAT	SO YD	456	456						60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	2448	2448						60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	25	25					
42400800	DETECTABLE WARNINGS	SO FT	314	314						60404950	FRAMES AND GRATES, TYPE 24	EACH	5	5					
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	841	841						67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	109572	109572						67100100	MOBILIZATION	L SUM	1	1					
										70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
										70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					

FILE NAME =	USER NAME = mltrnsds	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\p\work\how\mltrnsds\0238722-D0631-rtr\p0238722.dwg	DRAWN -	REVISED -	876			2010-095-RS	COOK	30	3	
PLOT SCALE = 100,0000' / 1"	CHECKED -	REVISED -	CONTRACT NO. 60L96							
PLOT DATE = 5/30/2014	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		

\* SPECIALTY ITEMS