



LEGEND		NOTES:	
1	LINE 4" (YELLOW SOLID LINE)	10	LINE 12" (WHITE DIAGONAL LINE)
2	LINE 4" (DOUBLE YELLOW SOLID LINES)	11	LINE 12" (YELLOW DIAGONAL LINE)
3	LINE 4" (YELLOW - 10' DASH, 30' SKIP)	12	LINE 24" (WHITE SOLID LINE)
4	LINE 4" (WHITE LANE LINE - 10' DASH, 30' SKIP)	13	LETTERS AND SYMBOLS (TYP.)
5	LINE 4" (WHITE SOLID LINE)	•••••	TOPSOIL, FURNISH AND PLACE 4" & SEEDING, CLASS 2A
6	LINE 6" (WHITE SOLID LINE)		
7	LINE 6" (WHITE LANE LINE - 2' DASH, 6' SKIP)		
8	LINE 8" (WHITE SOLID LINE)		
9	LINE 12" (WHITE SOLID LINE)		

- ALL PAVEMENT MARKINGS SHALL BE THERMOPLASTIC UNLESS OTHERWISE SPECIFIED.
- RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE USED THROUGHOUT THE PROJECT LIMITS. SEE DISTRICT DETAIL TC-11.



COMPANY NAME: HRGreen  
 PROJECT CONTACT: HRGreen.com  
 DATE PLOTTED: 5/23/2014 11:50:45 AM  
 FILE NAME: 86100196.10-pm-07.dgn  
 PLOT DRIVER: pafefit  
 PEN TABLE: standard-trans.tbl



USER NAME = dstencz	DESIGNED - J. ATTANASEO	REVISED -
FILE NAME = 86100196.10-pm-07.dgn	DRAWN - J. ATTANASEO	REVISED -
PLOT SCALE = 1" = 50'	CHECKED - T. HAMILTON	REVISED -
PLOT DATE = 5/23/2014	DATE - 5/23/14	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**PAVEMENT MARKING AND RESTORATION PLAN**  
**US ROUTE 12 (ELA RD. TO LAKE COOK RD.)**  
 SCALE: 1" = 50'    SHEET NO. 7 OF 8 SHEETS    STA. 304+00 TO STA. 334+00

F.A.P. RTE. 334	SECTION SY-3-RS-4	COUNTY LAKE	TOTAL SHEETS 104	SHEET NO. 25
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60N26	