


- 12' SECTION OF GUARDRAIL LOCATE AT ALL NON-SPLICE MOUNTING POINTS

GALVANIZED STEEL PLATE $1\frac{3}{4}$ " \times 3" \times $\frac{1}{8}$ " AT ALL POST MOUNTING BOLTS

NOTE:

DIAMOND TIPPED DRILL SHALL BE USED TO DRILL THRU REINFORCEMENT BARS





POSTS SHALL BE HOT DIPPED GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM DESIGNATIONS A-123 AND A-385.

TWO PERCENT (2%) OF ALL ANCHOR BOLTS SHALL BE TEST LOADED IN PLACE. MIN. TEST LOAD = 8 KIPS.

ALL BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED IN ACCORDANCE WITH ASTM DESIGNATION A-153.

FOR MATERIAL COMPOSITION OF PREFABRICATED PAD, SEE ARTICLE 54.9(F), (BEARING AND ANCHORAGE), OF THE STANDARD SPECIFICATIONS.

PROVIDE 1-1/8" AND 2-1/16" GALVANIZED STEEL SHIMS FOR 25% OF THE POSTS.

IF ONE ANCHOR BOLT FAILS DURING TEST, TWO OTHER ANCHOR BOLTS SHALL BE TESTED. TESTING EQUIPMENT CAN BE OBTAINED FROM BOLT COMPANIES.

THIS SHEET IS FOR INFORMATION ONLY

FILE NAME =	USER NAME = galbanjr	DESIGNED -	REVISED - R. RITCHIE 05-02-00		TYPICAL DETAIL FOR CENTER LONGITUDINAL JOINT		F.A.P.	SECTION	COUNTY	CHEETC	SHEET
c:\pw_work\pwidot\galbanjr\d0249591\Dis	Std.dgn	DRAWN - RFL	REVISED -	STATE OF ILLINOIS			112	MY-RS-1	WILL	35	26
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	GUARDRAIL JOINT			BM-05	CONTRACT NO. 60N4)N42
	PLOT DATE = 5/23/2014	DATE - 10-31-88	REVISED -		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. ROAD	D DIST. NO. 1 ILLINOIS FED. AII	D. AID PROJECT		