


URBAN
100% STATE

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0044 DRAINAGE
20101000	TEMPORARY FENCE	FOOT	95	95
20101100	TREE TRUNK PROTECTION	EACH	3	3
20101200	TREE ROOT PRUNING	EACH	1	1
20800150	TRENCH BACKFILL	CU YD	390	390
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	121	121
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2	2
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2	2
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2	2
25200110	SODDING, SALT TOLERANT	SO YD	121	121
25200200	SUPPLEMENTAL WATERING	UNIT	6	6
28000400	PERIMETER EROSION BARRIER	FOOT	396	396
28000510	INLET FILTERS	EACH	14	14
28100107	STONE RIPRAP, CLASS A4	SO YD	7	7
28200200	FILTER FABRIC	SO YD	7	7
30300118	AGGREGATE SUBGRADE IMPROVEMENT 18"	SO YD	132	132
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SO YD	58	58
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	20	20
42001300	PROTECTIVE COAT	SO YD	34	34
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	51	51

URBAN
100% STATE

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0044 DRAINAGE
44000300	CURB REMOVAL	FOOT	16	16
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	80	80
44000600	SIDEWALK REMOVAL	SO FT	51	51
44002206	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 1 1/2"	SO YD	66	66
44002208	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2"	SO YD	128	128
44201682	CLASS D PATCHES, TYPE II, 3 INCH	SO YD	8	8
44201684	CLASS D PATCHES, TYPE IV, 3 INCH	SO YD	49	49
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	38	38
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	71	71
54261224	CONCRETE END SECTION, STANDARD 542001, 24", 1:2	EACH	1	1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	28	28
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	25	25
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	81	81
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	7	7
550A1010	STORM SEWERS, CLASS A, TYPE 4 24"	FOOT	164	164
55200900	STORM SEWERS JACKED IN PLACE, 24"	FOOT	25	25
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	4	4
60221100	MANHOLES, TYPE A, 5*DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2
60224446	MANHOLES, TYPE A, 7*DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1

12/14/2013 PM
12/17/2013



USER NAME = 1405	DESIGNED - RS	REVISED -
PLDT SCALE = 100.0000 1/1 in.	DRAWN - ED	REVISED -
PLDT DATE = 12/11/2013	CHECKED - RS	REVISED -
	DATE - 12/17/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

McCORMICK BLVD - HOWARD STREET TO TOUHY AVENUE
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.U. RTE. 0378	SECTION 3738-T	COUNTY COOK	TOTAL SHEETS 28	SHEET NO. 3
CONTRACT NO. 60R87			ILLINOIS FED. AID PROJECT	