

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES						CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	84	84					44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	316	316				
25200110	SODDING, SALT TOLERANT	SO YD	84	84					44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	840	840				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	108	108					44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	735	735				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3025	3025					44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	525	525				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					60250200	CATCH BASINS TO BE ADJUSTED	EACH	38	38				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	610	610					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	72	72					67100100	MOBILIZATION	L SUM	1	1				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	7059	7059					70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
42001300	PROTECTIVE COAT	SO YD	167	167					70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	40	40					70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1				
42400800	DETECTABLE WARNINGS	SO FT	358	358					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	69933	69933					70300100	SHORT TERM PAVEMENT MARKING	FOOT	5635	5635				
44000600	SIDEWALK REMOVAL	SO FT	40	40					70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	950	950				

FILE NAME: c:\p\ur\1\p\ur\gobon\1\40293296\027012-ur\sc\table.dgn	USER NAME: gobonj	DESIGNED: -	REVISED: -
PLOT SCALE: 1/8" = 1'-0"		DRAWN: -	REVISED: -
PLOT DATE: 5/30/2004		CHECKED: -	REVISED: -
		DATE: -	REVISED: -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**BARRINGTON RD. (US RTE. 20 TO SCHAUMBURG RD)  
SUMMARY OF QUANTITIES**

F.A.P. RTE. 362	SECTION 0105RS-3	COUNTY COOK	TOTAL SHEETS 29	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. OF SHEETS STA. TO STA.