

NOTES:

- 1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
- 2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

- 1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
- 2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
- 3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

SEQUENCE OF CONSTRUCTION (MILLING FIRST)

- 1. MILL HMA FIRST IF THERE IS AT LEAST 41/2 INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
- 2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| Γ | FILE NAME = | USER NAME = galbanjr | DESIGNED - R. SHAH | REVISED - A. ABBAS 04-27-98 | | PAVEMENT PATCHING FOR | F.A.P. SI | ECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|-------------------------------|--------------------|-----------------------------|------------------------------|--|---|---------|----------|-----------------|--------------|
| | c:\pw_work\pwidot\galbanjr\d0293296\Dis | Std.dgn | DRAWN - | REVISED - R. BORO 01-01-07 | STATE OF ILLINOIS | | 362 01 | 105RS-3 | соок | 29 | 19 |
| | | PLOT SCALE = 100.0000 ' / in. | CHECKED - | REVISED - R. BORO 09-04-07 | DEPARTMENT OF TRANSPORTATION | HMA SURFACED PAVEMENT | BD400-04 | (BD-22) | CONTRACT | NO. 6 | 50R96 |
| | | PLOT DATE = 5/30/2014 | DATE - 10-25-94 | REVISED - K. ENG 10-27-08 | | SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA. | FED. ROAD DIST, NO. 1 ILLINOIS FED. AID PROJECT | | | | |