

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				0004	0021	0021	0021	0021		
				80% FEDERAL	80% FEDERAL	80% FEDERAL	100% VILLAGE OF	80% FEDERAL		
				20% STATE	20% STATE	20% STATE	PINGREE GROVE	20% STATE		
ROADWAY	TRAFFIC	INTERCONNECT	FIRE PROT. DIST.	LIGHTING						
35600710	HOT-MIX ASPHALT BASE COURSE WIDENING, 8 1/2"	SO YD	3,548	3,548						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	70	70						
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	869	869						
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	182	182						
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	215	215						
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	27	27						
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,578	2,578						
42001300	PROTECTIVE COAT	SO YD	11	11						
44000100	PAVEMENT REMOVAL	SO YD	4,777	4,777						
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	17,024	17,024						
44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2"	SO YD	1,691	1,691						
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	681	681						
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	341	341						

FILE NAME: #FILES#
SMT_PLAN

13

USER NAME: #USER#	DESIGNED - MTM	REVISED -
DRAWN - MTM	CHECKED - BA	REVISED -
PLOT SCALE: #SCALE#	DATE - 3/31/14	REVISED -
PLOT DATE: #DATE#		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 3 OF 13 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	106-S-N-2	KANE	147	6
CONTRACT NO. 60T09				
ILLINOIS FED. AID PROJECT				

REV.